

# Contents

I.		Overvi	ew	
	SE	CTION		
		1.1.	Governance and Board Members	l-1
		1.2.	Management Team	I-1
		1.3.	Service Area and Customer Relationships	I-2
	SE	CTION	2 Capital Improvement Planl-	.2
		2.1.	Calendar	I-3
		2.2.	Funded Portion of the Programs	I-3
		2.3.	Internal Development Process	I-3
		2.4.	Project Status Description	I-4
		2.5.	Project Categories	I-5
II.		Capital	Improvement PlanI	I-1
	SE	CTION	1 Approval ProcessII-	·1
	SE	CTION	2 Financial Plan IntroductionII-	1
	SE	CTION		,
	SE	CTION	4 The Project ProcessII-	4
		4.1.	Project Identification	
		4.2.	Project Proposals	
		4.3.	Project Prioritization	<b> -4</b>
Ш		Capital	Improvement ProjectsII	
		1.1.	Water Field ServicesII	I-1
		1.2.	Customer Meter Replacement ProgramII	I-1
		1.3.	Fire Hydrant Replacement ProgramIII	I-2
	SE	CTION	2 SewerIII-	.5
		2.1.	Sewer Field ServicesII	I-5
		2.2.	CSO ControlIII	I-5
		2.3.	Pump StationsII	I-6

SE	CTION 3.1	3 Central Services Error! Bookmark not defined Information TechnologyError! Bookmark not defined	
	3.2 define		ot
	3.3	FacilitiesError! Bookmark not define	d.
IV.	Appen	dicesIV	-4
Glo	ssary		
BOV	۷C	Board of Water Commissioners	
CIP.	<b></b>	Capital Improvement Plan/Program/Project	
		(depending on context)	
		Consultant Services	
		Detroit Land Bank Authority	
		Detroit Public Schools Community District	
		Detroit Edison	
		Drinking Water Revolving Fund	
DWS	οD	Detroit Water and Sewerage Department (Department)	
ראים	:	Department of Water Supply	
		Fiscal Year	
		Grandmont Rosedale Development Corporation	
		Great Lakes Water Authority (Authority)	
		Green Stormwater Infrastructure	
I&E.		Improvement and Extension	
		Master Bond Ordinance	
NPD	ES	National Pollutant Discharge Elimination System	
PASI	ER	Pavement Surface Evaluation and Rating	
PDD		Planning and Development Department	
PW.		Public Works	
SRF.		State Revolving Fund	
URT		Upper Rouge Tunnel	
W/S		Water System	







## **EXECUTIVE SUMMARY**

January 1, 2016 marked a new era for the Detroit Water and Sewerage Department (DWSD). The creation of the Great Lakes Water Authority (GLWA), a regional supplier of water and wastewater treatment services, led to the evolution of DWSD as a retail only service provider for the City of Detroit. The new DWSD is solely focused on ensuring affordability and improving service to Detroit customers. Over the past five years, the department has implemented compassionate customer service through staff training and launched the Water Residential Assistance Program. Through improved business practices and outreach efforts to reduce delinquent bills, the department increased the collection rate to 92% (up from 77% in January 2016). This increased collection rate, is equivalent to approximately \$4 million dollars for every percentage point. Increased collections were made possible by offering customers multiple avenues to make payments, including mail, online, in-person, by kiosk, or by phone, as well as through outreach efforts at community partners such as faith-based organizations. As of March 2020, the department no longer processes in-person payments due to the COVID-19 pandemic.

Improved collections allows the department to invest more in the operations, maintenance, renewal and replacement of the water and sewer infrastructure. With respect to operations and maintenance, DWSD has cleaned more than 30,000 catch basins in a 3 year time span; ensured a 98% availability rate for operable fire hydrants, resolved more than 90% of running water complaints in 2 days or less; and repaired 87% of broken water mains reported by customers in 4 days or less. In addition, the department has become

completely paperless, implementing Cityworks for work order management. However, Cityworks would be useless without the investment in updating the Geographic Information System (GIS) which contains the data on the size, length, installation date, location, etc. of the DWSD water and sewer infrastructure. DWSD crews have been trained to use tablets in the field to update the GIS maps.

DWSD launched an aggressive program to renew 1% of the systems infrastructure in July 2017 with the launch of the \$500 million Capital Improvement Program Management Office (CIPMO). The engineering, stormwater management group, construction and facilities teams updated standard details, specifications, and standard operating procedures for all capital construction. This included implementation of e-builder, a construction project management software platform, which digitized the entire construction administration process. All schedules, submittals, invoices, change orders, meeting minutes, and daily inspection reports are housed in e-builder. This allows for more transparency across DWSD divisions such as finance and legal. These efforts involved Public Affairs in creating new procedures for outreach prior to, during and after construction projects and preventative maintenance work.

DWSD also updated the process by which projects are chosen for replacement, creating a water risk model that accounts for break history, probability of lead service lines, materials of construction, age of pipe, capacity, available fire flow etc. and a sewer risk model that includes basement back up complaints, materials of construction, capacity, untreated combined sewer overflow discharge, age of pipe etc. Both models include categories for investments in an area by other municipal agencies (city, state and federal); private corporations or the philanthropic community.

DWSD also performs condition assessments to determine the specific renewal or replacement needs for water and sewer infrastructure. This new program has resulted in the following for calendar years 2018 through 2020:

- 66 Miles of water main replaced (22 miles per year, up from 5 miles per year in 2016)
- 50 miles of sewer lined (17 miles per year, up from 3 miles per year in 2016)
- 1,100 full lead service line replacements
- 75 Miles of water main assessed
- 295 miles of sewer main assessed
- 240 sewer segment capital rehabilitation repairs

DWSD also began an aggressive program to implement green stormwater infrastructure (GSI) for stormwater management in accordance with its National Pollutant Discharge Elimination System (NPDES) Permit issued by the Michigan Department of Energy, Great Lakes, and Environment (EGLE). The permit requires the department to spend \$50 million on GSI implementation by 2029. This requirement was included in the 2008 permit and as of January 2016 the department had only invested \$1.3 million in GSI including demolition of vacant structures in the Brightmoor neighborhood and planting trees throughout Rouge Park and in various westside neighborhoods. At the end of calendar year 2020, the department has constructed 16 GSI projects which manage 61.5 million gallons of stormwater annually. These projects have a capital investment of nearly \$20 million. This included the 2020 project that transformed 10 medians on Oakman Boulevard into bioretention, managing 37 million gallons of stormwater annually. The department's largest GSI project to date will begin construction this calendar year in the Far West neighborhood adjacent to Rouge Park. This project will

manage stormwater for a 218 acre area with detention ponds located in the park. The project is valued at more than \$30 million and will allow the department to meet its permit obligation by 2027; two years earlier than required.

Motivated by visionary leadership and resolute fortitude, DWSD team has been able to accomplish unimaginable heights in five short years. The work has been possible because of a concerted effort to focus on our customers. DWSD proudly presents the 2022 to 2027 Five-Year Capital Improvement Program





### **O**VERVIEW

#### SECTION 1 **DETROIT WATER AND SEWERAGE DEPARTMENT**

Detroit Water and Sewerage Department (DWSD) is one of the largest water and sewer utilities in the United States, serving more than 235,000 accounts that includes a residential population of nearly 700,000. DWSD's water network consists of more than 2,700 miles of water main and nearly 3,000 miles of sewer collection piping. DWSD has a rich history as a public utility dating back to 1836. Today, DWSD focuses on improving the service of account holders in the city of Detroit. This includes deployment of kiosks for bill payment throughout the city, use of "Improve Detroit" (See-Click-Fix) to report water and sewer issues, and stronger partnerships with other city agencies to address citizen's issues. The source water in the Detroit area is obtained from two sources: Lake St. Clair and the Detroit River.

On January 1, 2016, the City of Detroit began leasing regional water and sewer infrastructure, as well as water and wastewater treatment facilities, to the Great Lakes Water Authority (GLWA). The regional system, built by DWSD, serves 126 municipalities in seven southeast Michigan counties. The agreement between DWSD and GLWA includes a \$50 million annual lease payment for 40 years to replace and rehabilitate DWSD's aging water and sewer system. DWSD continues to retain ownership of the regional assets.

The governance structure of the Authority gives suburban water and sewer customers a substantial collaborative role in the direction of one of the largest water and wastewater utilities in the nation. While GLWA manages and operates all regional water and wastewater wholesale services, DWSD and the other customers retain control of the local water and sewer services within their respective borders. DWSD also acts as an agent of GLWA with respect to rate-setting,

billing, collecting and enforcing local retail charges in the City of Detroit.

#### Governance and Board Members 1.1.

The seven members of the Board of Water Commissioners (BOWC) are appointed by and serve at the pleasure of the Mayor of the City of Detroit. In addition to the qualifications established in the December 15, 2015 Court Order, the City's Charter: (i) prohibits any member of the Board from being a City official or employee, or a principal or employee of a contractor of the City, (ii) requires that a member of the Board be a citizen of the United States and a resident of the State of Michigan, and all seven current commissioners are Detroit residents, appointed by the Mayor.

Four committees have been established: (i) Customer Service, (ii) Human Resources, (iii) Finance, and (iv) Capital Improvement Program and Operations Committee. The BOWC currently consists of:

- Michael Einheuser, Chairman
- Mary E. Blackmon, Vice Chairperson
- Lane Coleman, Commissioner
- John Henry Davis, Commissioner
- Linda D. Forte, Commissioner
- Jane C. Garcia, Commissioner
- Jonathan C. Kinloch, Commissioner

#### Management Team 1.2.

To meet the needs of Detroit's residents and businesses, DWSD is led by a Management Team consisting of:

- Gary A. Brown, Director
- Palencia Mobley, P.E., Deputy Director and Chief Engineer

- Samuel Smalley, P.E., Chief Operating Officer
- Thomas Naughton, Chief Financial Officer
- Dan Rainey, Chief Information Officer
- Debra Pospiech, General Counsel

#### Service Area and Customer Relationships 1.3.

The service area of DWSD is primarily the city of Detroit. This includes more than 235,000 customers in a 139-square mile area. However, DWSD does have approximately 200 suburban retail customers. Suburban retail customer are those who lie outside the incorporated limits of the city but are served by the DWSD's local water or sewer infrastructure. DWSD is committed to serving all of its customers, both residential and non-residential, with superior service.

#### SECTION 2 CAPITAL IMPROVEMENT PLAN

The DWSD Capital Improvement Program (CIP) annually compiles, evaluates and guides future capital investment in programs and projects that will upgrade the Department's aging water distribution and wastewater collection system infrastructure, stormwater management infrastructure, facility improvement and upgrades, as well as the various vehicle and equipment procurements that supports the DWSD systems over a five year timeframe. The CIP ensures mandated projects and rehabilitation of assets necessary to meet permit obligations, funding sources and other regulatory requirements are aligned. Based upon the execution of programs and projects identified in the CIP, existing levels of service currently provided will be met or exceeded.

This CIP should be considered a planning document – the CIP is a dynamic and evolving plan that requires continual review and adjustments as needs become more defined throughout the year. The estimates indicated in the early years of the report are likely more precise than those in the later years. All of which help plan the capital program cash flow needs. The project descriptions and summaries represent a brief synopsis of the entire project scope; these descriptions are generally more precise for ongoing active projects than for planned new projects, where specific project activities may have yet to be determined.

DWSD has developed a CIP for the next five years that is within the range of \$75 to \$100 million, annually, to accelerate the pace of infrastructure renewal. In fact, the CIP is a major component of the City's larger capital investment strategy designed to:

- Renew and rehabilitate Detroit infrastructure and neighborhoods
- Reconfigure systems to reflect demographic trends and emerging urban plans
- Re-landscape the urban environment to embrace the greening of Detroit"

A centerpiece of the CIP was the implementation of a CIP program management organization (CIPMO) with responsibility to coordinate and execute capital project planning and implementation across public agencies and private utilities respon7sible for infrastructure and community development. DWSD through the CIPMO is establishing a sustainable and repeatable process for capital project development and delivery, through updated design standards and utilization of a group of standard Engineers Joint Contract Documents Committee (EJCDC) series documents for construction and professional services. This has been a multi-year process that is intended to produce an annual program that is scalable to relate to DWSD's planned capital budget and infrastructure co-ordination across the City.

As the CIPMO established improved business process workflows, developed standard operating procedures, implemented a cloud based technology infrastructure and delivered designs and construction bid packages, parallel work continued by DWSD staff to implement water, sewer and green stormwater infrastructure projects. DWSD has and will continue to make investments in

equipment, facilities, and technology to improve the level of service to its customers and maximize the life of its assets. Field Engineering Services (FES), which is responsible for water and sewer CIP delivery, is now focusing on transitioning efforts of the CIPMO to internal staff over a two-year period.

DWSD also developed and submitted to State of Michigan Environment, Great Lakes and Energy (EGLE) an Asset Management Program that satisfies the requirements outlined in the Safe Drinking Water Act 1976 PA 399 as amended; R 325 11606. The categories include Asset Inventory, Criticality Assessment, Level of Service Goals, Capital Improvement Plan, Funding Structure and Rate Methodology.

#### 2.1. Calendar

The following are some important dates regarding the DWSD 2022-2026 CIP.

Date	Description
February 2, 2021	Submitted FY2022-2026 CIP Preliminary Draft to GLWA as per Lease Agreement
February 17, 2021	Board of Water Commissioners Meeting- Presented FY2022-2026 CIP Preliminary Draft
April 21, 2021	Present Board of Water Commissioners Meeting- submit draft of FY2022-2026 CIP
May 19, 2021	Board of Water Commissioners Meeting- Proposed Approval of FY2022-2026 CIP
June 25, 2021	Submit BOWC Approved FY2022-2026 CIP to GLWA, FRC and City of Detroit
July 1, 2021	Effective Date of FY 2022-2026 CIP

#### Funded Portion of the Programs 2.2.

The source of funds for the CIP include revenue financing also known as the Improvement & Extension (I&E) fund, bond proceeds, loan, and grant opportunities.

This plan spans a 5-year period from fiscal year 2022 through 2026. The CIP is used as a cash flow prediction and serves as the basis for timing the need for bond proceeds or low-interest loans from the State (SRF) and Drinking Water Revolving Fund (DWRF). Some construction projects are currently funded from prior bond sales settled at bifurcation with GLWA. The sale of bonds and loan applications are authorized jointly by the DWSD and GLWA boards.

DWSD will continue to explore new and creative ways of seeking additional funding, including applying for grants from federal, state and nonprofit organizations.

The CIP review process also includes an extensive review of the total project, or "lifetime" budget, which reflects historical spending prior to, during, and beyond the current 5-year period. The goal of the Department's capital financing strategy is to align capital project financing sources with multiple objectives including: (1) recovering the costs of capital investment over the useful life of the capital assets; (b) minimizing the impact of the capital programs on water and sewage revenue requirements; (c) protecting and enhancing the Department's financial position; and (d) minimizing financial impacts through orderly phased implementation. The potential funding source identified for each project is subject to change based upon the systems need and financial resources available at the time.

#### 2.3. **Internal Development Process**

The CIP development process begins in the fall of each year. The Finance Department's Asset Management Group sends out CIP request packages and instructions to the Executive Management Team requesting submission of projects and updates to existing

<b>Project Status</b>	Description
New	Project that has never been included in a previous CIP.
Not Yet Started	Project that has been included in the previous CIP, has never had expenditures charged to it and does not have an assigned Oracle Fusion Project Number. Pre-development planning or preliminary engineering in progress.
Under Procurement	Project that has an assigned Oracle Fusion Project Number and has not been issued a Notice to Start Work. Detailed design completed.
Active	Project that has an assigned Oracle Fusion Project Number in the financial system, a Notice to Start Work has been issued, had expenditures in the last fiscal year and has projected expenditures of more than \$100,000 in the current fiscal year. Construction is active or implementation started.
On-Hold	Project that has been suspended, may or may not have an assigned Oracle Fusion Project Number, experienced expenditures or no expenditures in the previous fiscal year(s), and/or has no projected expenditures in the current fiscal year or future fiscal years.
Pending Close-out	Project that has an assigned Oracle Fusion Project Number, a Notice to Start Work has been issued, has projected expenditures for the current fiscal year equal to \$100,000 or less - with no future projected expenditures and has reached substantial completion.

projects. The packages are due back late October then compiled for further internal reviews and financial analysis. Projects are prioritized based on historical trends for those assets as well as service levels. Once developed the CIP is introduced to the BOWC Committees for further review and final approval.

#### 2.4. **Project Status Description**

A status is assigned to each project within the CIP to show the high level progress from planning to completion. Some projects are divided into multiple phases or categories based upon the contract type. As such, each phase of a multiple phase project will have its own status and contract number. Descriptions of each particular status are provided in Table 1-1.

Table I-1. Project Status Descriptions

#### 2.5. **Project Categories**

Some construction projects are broken up into several phases related to how the particular project will be delivered and managed. Categories may be grouped to align with work to be performed within each individual phase. Individual categories are identified and named below, however, in reality several categories may exist for each phase. In this case, this implies the same vendor, under one contract, will be performing multiple categories of the overall project. The current project categories are identified below.

S	Study		
D	Design		
C	Construction		
CA	Construction Assista	ance	
DB	Design and Build		
DBA	Design Build Assista	nce	
CM	Construction Manag	gement	
MOU	Memorandum of	Understanding	Agreements
(coordinatio	on with other City of I	Detroit departm	ents, utilities
or other age	encies)		
PO	Purchase Order		

### **CIP Types**

Multiple CIP types are necessary to distinguish the differences in intent of how a particular CIP is to be used. This CIP contains three primary CIP types; Project, Program and Allowance. A typical project that has a specific scope and timeframe is considered a Project. Whereas Programs and Allowances do not have specifically developed scopes and typically extend over many years. Allowances are necessary for utility operations due to the unanticipated nature of pipeline and equipment failures that require immediate repair and rehabilitation to continuously meet level of service requirements. Table I-2 CIP Types defines each CIP Type.

Table I-2. CIP Types

CIP Type	Description
Project	A "Project" consists of the replacement and/or rehabilitation of specific capital assets within a finite timeframe and scope.
Program	A "Program" consists of the replacement and/or rehabilitation of specific capital assets on an ongoing or recurring basis. The program scope and/or projected expenses may vary from year-to-year depending on the needs identified within the program and as newly established programs develop consistent schedules, requirements and history over time. Although not typically identified in the CIP futures years projected expenses, these programs will typically be funded in perpetuity.
Allowance	An "Allowance" consists of unanticipated replacement and/or rehabilitation of currently unidentified capital assets. Engineering studies, evaluations, testing, construction assistance directly related to the unforeseen replacement or rehabilitation are also included in the projected expenses.

## CAPITAL IMPROVEMENT PLAN

#### SECTION 1 **APPROVAL PROCESS**

The CIP development and approval process begins with the approval of the previous year's CIP. The CIP process is a substantial level of effort that involves many people throughout the Department. Modifications, adjustments and improvements are being continuously considered and vetted internally and externally, in coordination with other City of Detroit agencies, utilities, or other system customers. Projects and programs that ultimately get funded within the CIP are typically identified based upon master planning or condition/need assessment efforts. Projects also are identified internally based upon the needs of engineers, operations or maintenance staff. The process typically begins in the fall of each year where project managers review project needs through the completion of the Capital Improvement Plan Project Proposal (CIPPP). CIPPP's are due to the Chief Engineer by the end of October. At this time, the Chief Engineer will make requests to Finance to issue CIP numbers for each project that can be added as new projects to the CIP. Preparation of a draft of the CIP and back-up documentation is reviewed internally with Management, and other city agencies as required. DWSD's CIP upcoming capital budget is submitted to the City of Detroit, Office of the Chief Financial Officer in November for presentation to the Detroit City Council for the City's five year CIP Budget.

The Preliminary Draft CIP is introduced to the BOWC no later than its February Capital Improvement Committee meeting. An approval version of the CIP is presented to the BOWC by its May meeting. In accordance to the Lease Agreement with GLWA the DWSD preliminary draft CIP is submitted to the GLWA Chief Planning Officer and Manager of Capital Programs on February 1. If necessary an updated version will be adopted by the BOWC at its February meeting, and a final CIP document will be submitted to GLWA on

March 1. At this point, it is expected that the CIP approval process coincides with the overall budget development process.

#### SECTION 2 **FINANCIAL PLAN INTRODUCTION**

The Fiscal Year 2022-2026 CIP is planned for approval submission to the Board in May 2021. The following table details the planned expenditures and the projected funding sources for the Fiscal Year 2022-2026 CIP. Expenditures are focused on replacement, installation and/or abandonment of existing water mains, replacement of inoperable fire hydrants, rehabilitation of sewer systems, management of storm water with green infrastructure, upgrades to information technology systems, replacing aging equipment and vehicles, as well as rehabilitation of facilities that support the operation of the utility. The Department will finance its ongoing CIP with proceeds of existing bonds, future bond issues by the GLWA on behalf of DWSD, lease payments from GLWA, federal and state grants, loans and revenues of the Water Supply and Sewer System.

The DWSD CIP financing plan balances a number of objectives to support the Departments' mission to efficiently deliver the best retail water and sewer services in partnership with our customers through excellence in service and collaboration. Those objectives include the following.

- ✓ Working with a cross-functional team, identify and fund prioritized capital improvements to ensure a sustainable system.
- ✓ Recover the costs of capital investment over the useful lives of the capital assets.
- Minimize the financial impact of the capital programs on system customers.

✓ Protect and enhance the Departments' financial position.

The DWSD works with the Authority to draw upon four sources of revenue for its capital improvement plan.

- 1. Bond Proceeds: The Authority uses an incremental method of funding long-lived capital projects through a bond financing program rather than funding all projects in advance. The Authority issues revenue bonds pursuant to Michigan Public Act 94 of 1933 (the Revenue Bond Act). The Act provides a pledge of "net revenues" for the payment of the bond principal and interest. "Net revenues" means the revenues of the system remaining after deducting the reasonable expenses of administration, operation, and maintenance of the system.
- 2. Revenue Financed Capital: Based upon ongoing expense, capital, and revenue optimization efforts, the DWSD is able to build reserves to fund pay-as-you go capital for shorterlived and lower-dollar capital expenditures.
- 3. Federal Loan Programs: The Authority's sources of funding includes lower cost financing programs including the State Revolving Fund (SRF) Loan program and the Drinking Water Revolving Fund (DWRF) Loan program. The lease agreement with the City of Detroit provides for use of SRF and DWRF for the benefit of the City of Detroit Local System. While the Authority is responsible for the debt service on bonds issued to finance capital improvements to the DWSD Local Water and Sewer System, the annual principal and interest requirements are included in the revenue requirements assigned to the City of Detroit retail customer class.
- 4. Grants: The DWSD utilizes public grants programs such as those available from the Environmental Protection Agency, Housing and Urban Development, as well as nonprofit organizations who fund programs in partnership with DWSD through the Detroit Economic Growth Corporation. DWSD

will continue to pursue opportunities which meet the mission of the organization to provide safe drinking water, reliable customer service and environmental integrity.

To ensure proper accountability of funding sources and uses, the Department utilizes two funds for its capital program for each system: the Construction Bond Fund and the Improvement & Extension (I&E) Fund.

- ✓ **Construction Bond Fund:** This fund represents the proceeds of bond issuances for the purposes of financing capital improvements.
- Improvement & Extension Fund: I&E fund is defined by the Water and Sewer Service Agreements as the "fund used for improvements, enlargements, extensions or betterment" of the System. Cash receipts of the Department are transferred into the I&E Fund pursuant to a flow of funds after commitments are met for a monthly allocation of System operations and maintenance expense, debt service, pension, water residential assistance program, budget stabilization fund, and extraordinary repair and replacement fund as administered by a trustee.

It should be noted that the basis of accounting for the CIP is the accrual basis. Under this basis of accounting, revenues are recognized when earned and measurable regardless of when collected; and expenses are recorded, or accrued, on a matching basis when incurred. Accrued expenses are expected to be paid in a subsequent accounting period. For purposes of this CIP, expenses and expenditures are used interchangeably.

#### SECTION 3 **SUMMARY CIP FINANCIAL PLAN REVIEW &** ANALYSIS

The FY 2022 - FY 2026 capital improvement plan provides for \$216 million of water system improvements and \$210 million of sewer system improvements over the five year planning cycle.



Table II-1. CIP Categories

Category Summary	% of 5-Year Spend	FY 2021	FY 2022	FY 2023	FY 2024	FY 2025	FY 2026	Total 5-Year 2022-2026
Water Main	33%	42,985	50,680	40,000	21,750	15,750	10,750	138,930
Sewer Line Replacement	30%	28,367	46,918	32,525	21,025	14,000	14,000	128,468
CIPMO	1%	8,280	5,590		-	-	-	5,590
Green Infrastructure	12%	12,470	14,773	11,723	8,843	9,995	6,995	52,329
Central Services	10%	23,912	13,970	8,235	6,500	6,500	6,500	41,705
Meters/ Fire Hydrants	3%	8,767	8,701	1,000	1,000	1,000	1,000	12,701
Repair/Restoration	11%	20,973	13,113	11,000	12,800	8,720	1,000	46,633
	100%	145,754	153,745	104,483	71,918	55,965	40,245	426,356
Water	59.1%	86,080	80,661	54,918	37,800	27,720	15,000	216,099
Sewer	<u>40.9%</u>	59,674	73,083	49,566	34,118	28,245	25,245	210,257
	100.0%	145,754	153,745	104,483	71,918	55,965	40,245	426,356

DRAFT April 7, 2021 II-3

#### **SECTION 4** THE PROJECT PROCESS

#### **Project Identification** 4.1.

Currently, projects to be considered for inclusion in each year of the CIP are identified by the subject matter expert engineers, project managers or operations managers. These engineers and managers utilize available institutional knowledge, data, operations and maintenance reports, need and condition assessments and master plans to identify the project need. Many come from projects that are already in the planning process or have been designed but not yet constructed. Others were recommended by staff or chosen based on work being planned by the public works, planning, parks and recreation, or the housing and revitalization departments in the City of Detroit. Some are driven by regulatory requirements. Some originated from several sources.

#### 4.2. **Project Proposals**

DWSD has a CIP project proposal template which is used to provide the background/history for the project, proposed and alternative solutions, along with the budget and schedule for a project. The process by which projects are submitted and evaluated for inclusion in the CIP has been revamped under CS-1812 CIPMO. DWSD now manages all of its water and sewer CIP works through cloud based platform, e-Builder; with all program related tracking information, key performance indicators and documents submittals done in this project management information system. Over the next fiscal year, DWSD intends to have all other divisions manage their CIP within e-Builder.

In addition, the CIPMO in conjunction with the Field Services PMO has developed an asset management program for DWSD to use to select and prioritize projects for inclusion in the CIP. This ability to forecast the tentative assessment, design and construction timelines for neighborhoods is a valuable piece of the information sharing done under the Infrastructure Coordination Team, which consists of other City of Detroit Agencies (e.g. DPW) and private sector utilities (e.g. DTE).

#### 4.3. **Project Prioritization**

In the 2021-2026 CIP, projects are prioritized based on a risk model that provides a data-driven quantitative framework for both water and sewer assets, ensuring that risk assessments are defensible, consistent, and repeatable. Asset risk is computed and then aggregated on a neighborhood basis. Finally, priority neighborhoods are selected by overlaying neighborhood risk with strategic and planning-level criteria (external factors) such as Strategic Neighborhood Fund (SNF) areas, Department of Public Works (DPW) projects, federally funded projects, and previous Capital Improvement Program Management Organization (CIPMO) work. The risk model will continue to evolve over time, reflecting improvements in existing data and new data sources as well as changes due to DWSD's desired representation, understanding, and tolerance of business risk.

With respect to green stormwater infrastructure, a variety of factors are used to determine the priority of a project. This includes, reports of street flooding, basement backup claims data, community engagement/neighborhood participation, and site location. As of this CIP, projects in the Upper Rouge Tunnel have a higher priority than those in other areas of the city.

Inherent in the prioritization process is the ability to leverage dollars in an efficient way. Thus, when and where possible projects may be worked into the capital construction programs of DPW, DTE, or other agencies such as Wayne County and the State of Michigan Department of Transportation.

# CAPITAL IMPROVEMENT PROJECTS

The DWSD CIP is organized by three categories: water system, sewer system, and centralized services. Projects in the water category are primarily for water main replacements, residential metering and the fire hydrant replacement program. Projects in the sewer category include rehabilitation of the sewer infrastructure and green stormwater infrastructure. Centralized services are allowances that facilitate improvements that benefit the support of both the water and sewer business with the purchase of fleet and heavy equipment, rehabilitation and improvements to facilities, and information technology upgrades to facilitate operations and implementation of the capital programs. The following pages provide an overview of the projects types in each category and individual project descriptions for most of the projects in this CIP.

There are 40 projects listed in the water portion of this CIP. This includes 32 Field Services projects and programs, 4 water meter replacement related program, a fire hydrant replacement program, and 3 Central Services projects. Following this explanatory portion is a list of the projects with estimated costs, a set of maps displaying locations where the work for the projects will take place, and a list of the locations of the projects on the map.

#### Water Field Services 1.1.

On the following pages, there are maps which denote the water main replacement projects in this year's CIP. DWSD has 6 active construction contracts, two of which will be completed before FY22 begins. These projects at their completion will result in the reconstruction of nearly 20 miles of water main. There are 4 projects in the procurement phase which at their completion will result in the reconstruction of 22 miles of water main.

In addition, there are 200 miles of pipe that are being evaluated for inclusion in future construction contracts. Of this, 75 miles are designed but may not meet all the criteria to warrant replacement at

this time. The remaining 125 miles are segments of main submitted by the Field Services Maintenance and Repair Division for replacement or have been submitted by DPW as roads that will be resurfaced in the 2021 and 2022 construction season. Once awarded. DWSD will use a consultant engineering firm, Contract CS-1921, to design water mains. Based on previous project sizes, DWSD anticipates the new water main replacement contracts identified to begin in FY22 and beyond to replace 20 miles of water main annually.

Contract CS-1812 as discussed previously, will accelerates the renewal rate of water main replacement to 30 to 45 miles per year. The pilot areas that are being evaluated by the CIPMO are also shown in the following pages. Page XX

### Customer Meter Replacement Program

DWSD replaces customer meters annually. There are more than 200,000 meters in the DWSD service area. Meters range in size from 5/8" to less than 24" in diameter. Meters are replaced for a variety of reasons, including failure due to age or other malfunctions. Meters generally have a life expectancy of 10 to 20 years, but this varies based on the volume of water that passes through the meter, which increases the wear and tear on the mechanical components. Thus decreasing the accuracy of the meter, which in turn becomes nonrevenue water. It is in DWSD's interest to proactively schedule planned replacement of meters and associated equipment to ensure accurate billing for water consumed. This also improve the accuracy of sewer billings as well.

DWSD will also investigate new metering technologies. Newer technologies have capabilities such as remote shut off which has the ability to reduce operations and maintenance cost associated with locating the curb stop to terminate service. This would ultimately

reduce surface restoration costs, when a curb stop has to be excavated to complete the shut.

#### Fire Hydrant Replacement Program 1.2.

In FY17 DWSD began the implementation of a robust fire hydrant inspection, repair and replacement program in a partnership with the Detroit Fire Department (DFD). This program has resulted in DWSD replacing approximately 150 hydrants each year that are found inoperable from DFD conducting inspections. This program allowed DWSD to test the integration of the Geographic Information System (GIS) with the Work Asset Management (WAM) system and institute a paperless repair and replacement process. With this program, less than 3% of the 30,000 hydrants within the city are in need of repair. This program is also one component of the city's project to improve the city's Insurance Services Office (ISO) fire protection score. The City of Detroit received an ISO rating of Class 04 in 2015 and as a result of the cooperation and partnership between the two departments, the City of Detroit received an ISO rating of Class 02 in 2018.





### Table III-1. Water CIP Projects

Total estimated cost (1000's)

### Water Project List 2022-2026 CIP

Description	Status	Source of Funds	2021-22	2022-23	2023-24	2024-25	2025-26	2022-2026 CIP Total	Percent of CIP
WS-703 Water Main Replacement (33,820 LF)	С	I&E	-	-	-	-	-	-	0.0%
WS-704 Water Main Replacement -along Outerdrive	С	Bond	-	-	-	-	-	-	0.0%
WS-705 Water Main Replacement-2-sections	С	Bond	-	-	-	-	-	-	0.0%
WS-706 Water Main Replacement Wayne Co. Roads	С	Bond	-	-	-	-	-	-	0.0%
WS-707 Water Main Replacement- (20,000LF)	С	Loan (DWRF)	-	-	-	-	-	-	0.0%
WS-710 Water Main Replacement-Incl Wayne Co Roads	Α	Loan (DWRF)	1,000	100		-	-	1,100	0.5%
WS-711 Water Main Replacement-Incl Jefferson Streetscape	Α	Loan (DWRF)	4,200	1,000	-	-	-	5,200	2.4%
WS-712 Water Main Replacement-Cornerstone Village	Α	I&E/Bond	7,630	3,500	-	-	-	11,130	5.2%
WS-713 Water Main Replacement-Jefferson/Chalmers	N	DWRF	7,500	7,500	-	-	-	15,000	6.9%
WS-714 Water Main Replacement-MDOT Streetscape	С	DWRF		-	-	-	-	-	0.0%
WS-715 Pilot Areas-Riverdale, Minock, Miller & Rosedale	Ν	DWRF/I&E	6,900	7,000	3,000	-	-	16,900	7.8%
WS-718 WM New Center Commons & Virginia Park	Ν	DWRF/I&E	2,300	-	-	-	-	2,300	1.1%
DWS-907 Watermain & Sewer Rehab- North Rosedale Park	Α	I&E/Bond	5,000	-	-	-	-	5,000	2.3%
WS-720 Watermain Replacement-Various Streets	N◀	1&E/Bond	3,100	6,000	3,000	-	-	12,100	5.6%
WS-721 Lead Service Line Replacement	Ν	I&E/Bond	6,000	5,000		-	-	11,000	5.1%
WS-723 Lead Service Line Replacement for Settlements	N	Grant/Legal Settlements	800	200	-	-	-	1,000	0.5%
WS-725 Watermain Replacement-Medical Ctr, Cultural Ctr & Midtown 30,000LF	N	DWRF/Bond	-	4,000	5,000	5,000	-	14,000	6.5%
WS-702 Repair & Replacement of Water Mains	Α	I&E	-	-	-	-	-	-	0.0%
WS-708 Repair of Water Mains	A	I&E	-	-	-	-	-	-	0.0%
WS-717 Repair & Replacement of Water Mains (ws-702B)	N	I&E	4,000	3,000	3,000	3,000	-	13,000	6.0%
WS-719 Repair of Water Mains (WS-708/WS-702A)	N	I&E	-	-	2,000	2,000	-	4,000	1.9%
DWS-902 Repair of Pavement (break repair)	Α	I&E	1,920	-	-	-	-	1,920	0.9%
DWS-904 Repair of Lawns (break repair)	Α	I&E	1,500	-	-		-	1,500	0.7%
<b>DWS-919</b> (replace DWS-902)	N	I&E	4,080	6,800	6,800	2,720	-	20,400	9.4%

C = Closed, A = Active, P = Procurement, N = New, H = On Hold



Total estimated cost (1000's)

### Water Project List 2022-2026 CIP (Cont'd)

Description	Status	Source of Funds	2021-22	2022-23	2023-24	2024-25	2025-26	2022-2026 CIP Total	Percent of CIP
PC-808 West Warren (Constance at Rouge Park/Tireman Sawyer PH III)	Р	I&E	4,000	3,700	-	-	-	7,700	3.6%
CS-1909A-Condition Assessments-High Priority Neighborhoods	N	I&E	250	-		-	-	250	0.1%
CS-1921 Watermain/Sewer Design	N	I&E	1,000	1,000	1,000	-	-	3,000	1.4%
CS-1923 Third Party Inspection (Water & Sewer)	N	I&E	750	750	750	-	-	2,250	1.0%
CS-1947 Condition Assessment Sherwood Forest,	N	I&E	250	250				500	0.2%
CS-1812 Professional Engineering and Construction Services for CIPMO	А	I&E/Bond	2,795		-	· -	-	2,795	1.3%
Construction Program Management Allowances	N	I&E	-	-	1,000	750	750	2,500	1.2%
Watermain Program Allowances	N	I&E	-	-	8,000	10,000	10,000	28,000	13.0%
PC-803B Meter Installation	А	I&E			-	-		-	0.0%
Water Meter Replacement Program	Α	I&E	451	750	750	750	750	3,451	1.6%
Fire Hydrant Replacement Program	Α	J&E	250	250	250	250	250	1,250	0.6%
CS-1925 Itron Migration -MIU Replacement	Α	1&E	5,931	-	-	-	-	5,931	2.7%
CS-1926 Itron Migration Project Management	A◀	I&E	2,069	-	-	-	-	2,069	1.0%
Vehicle, Heavy Equipment, and Equipment Purchases	Α	I&E	1,335	1,500	1,500	1,500	1,500	7,335	3.4%
Information Technology	Α	I&E	1,890	1,618	750	750	750	5,757	2.7%
Facility Improvement Allowance	А	I&E	3,761	1,000	1,000	1,000	1,000	7,761	3.6%
		TOTALS	80,661	54,918	37,800	27,720	15,000	216,099	100.0%

C = Closed, A = Active, P = Procurement, N = New, H = On Hold

# **SECTION 2 SECTION 2**

#### **SEWER**

There are 40 projects listed in the Sewer portion of this CIP. This includes 11 Green Infrastructure projects and programs, 26 Field Services projects and programs, and 3 Central Services projects and programs. Following this explanatory portion is a list of the projects with estimated costs, a map displaying locations of Green Infrastructure projects, and descriptive sheets for Green Infrastructure projects.

#### 2.1. Sewer Field Services

DWSD has rehabilitated 15% of the 3,000 miles of sewer infrastructure through the non-invasive method of lining. In two previous fiscal years, the rate of renewal of the sewer infrastructure decreased due to financial constraints. With the execution of the lease agreement with GLWA, DWSD issued a new contract valued at \$20 million annually to rehabilitate the sewer system. Tasks are selected for the contractor based on water in basement claims and complaint data, as well as reports of cave-ins and sinkholes. The contractor will inspect via physical or robotic means and provide photo or video evidence of the results. The contractor will also submit a report with recommendations for rehabilitation of the sewer and manholes. DWSD will review all results and reports and issue a notice to proceed with the work as approved by the project engineer.

#### Combined Sewer Overflow (CSO) Control 2.2.

### Grey CSO Control

GLWA operates all wet weather (combined sewer overflow) facilities and associated appurtenances which serve DWSD and other Authority customers. There are 6 retention treatment basins and 3 screening and disinfection facilities. Of these only one facility, the Belle Isle CSO, solely serves the City of Detroit. Any grey CSO control projects will be found in the GLWA CIP document. DWSD's share of the cost for projects is allocated in the annual charges assigned by GLWA to its customers. Based on the 1999 Rate Settle Agreement, DWSD customers pay 83% of the cost for CSO facilities deemed to primarily serve the City of Detroit; with the exception of the Belle Isle CSO facility of which the cost is borne 100% by Detroit ratepayers.

### Green Stormwater Infrastructure for CSO Control

In 2008, DWSD was set to construct a tunnel to parallel the Rouge River to provide storage of combined sewage to eliminate untreated discharges. However due to financial constraints, the nearly \$1 billion tunnel project was replaced with a \$50 million GSI program. The issuance of the March 2013 NPDES Permit resulted in a commitment by DWSD to implement green stormwater infrastructure in the Upper Rouge Tunnel area of Detroit. The permit requires a \$30 million investment by 2019 with the remaining \$20 million investment completed by 2029.

The permit also includes a goal to remove 2.8 million gallons of stormwater from the combined sewer system. To date, projects implemented by DWSD, designed to manage the 2-year, 24-hour event (i.e. 2.34" of rainfall), have removed about 1.5 million gallons of stormwater in the URT. City wide, removal of impervious cover via demolitions and construction of GI practices on private property in conjunction with DWSD projects is estimated to remove 3 billion gallons of stormwater from the system annually.

In previous years, the DWSD CS-1522 GI Program Manager has issued the construction contracts for projects; however, in an effort to meet the spending requirements of the permit, DWSD will bid and award the remaining projects. Descriptions of both active construction projects and those in the design phase which will be procured this fiscal year are provided on the pages that follow.

#### 2.3. **Pump Stations**

There are four wastewater pump stations 3 of which service the City of Detroit only; (1) Belle Isle, (2) Fischer, and (3) Woodmere. (4) Bluehill serves Detroit and suburban customers. GLWA operates and maintains these pump stations via a shared service executed with DWSD. At this time, the need for capital investments in these facilities has not been identified. Upon receipt of the annual maintenance report from GLWA, DWSD will determine needs and program projects accordingly.

Table III 6. Sewer Projects

Total estimated cost (1000's)

Sewer Project List 2022-2026 CIP

Description	Status	Source of Funds	2021-22	2022-23	2023-24	2024-25	2025-26	2022-2026 CIP Total	Percent of CIP
DWS-903 Inspection and Rehabilitation of Sewers City Wide	Α	I&E/ Bond	7,000	-		-	-	7,000	3.4%
DWS-907 North Rosedale Park	Α	I&E/ Bond	1,013	_	-	-	-	1,013	0.5%
DWS-908 Cornerstone Village Sewer Rehab	Α	I&E/ Bond	2,693	-	-	-	-	2,693	1.3%
DWS-909 Sewer Condition assessments throughout City	С	I&E	-	-	-	-	-	-	0.0%
DWS-910- Sewer Condition Assessments High Priority	С	I&E			-	-	-	-	0.0%
DWS-916 Sewer Improvements in High Priority Neighborhoods	Α	SRF/ Bond	2,600	-	-	-	-	2,600	1.2%
DWS-917 Sewer Improvement in Riverdale	N	SRF/ Bond	5,000	4,800	300	-	-	10,100	4.8%
DWS-918 Sewer Improvements in Rosedale	N	SRF/ Bond	4,450	450	-	-	-	4,900	2.4%
DWS-920 Inspection and Rehabilitation of Sewers City Wide									
(Replace DWS-903)	N	I&E	3,000	8,000	4,000	-	_	15,000	7.2%
DWS-921 Electrical Monitoring Upgrades at Belle Isle,									
Woodmere, Fischer Sewage Pump Stations	Р	I&E	200	200	200	-	-	600	0.3%
DWS-926 Sewer Condition Assessments - West Village,									
Southwest Detroit, Michigan-Martin	Р	I&E	-	2,500	2,500	-	-	5,000	2.4%

C = Closed, A = Active, P = Procurement, N = New, H = On Hold



Total estimated cost (1000's)

### Sewer Project List 2022-2026 CIP

Total estimated cost (1000 s)		Sewel Project List 2022-2020 CIP								
Description	Status	Source of Funds	2021-22	2022-23	2023-24	2024-25	2025-26	2022-2026 CIP Total	Percent of CIP	
DWS-931 Roofing Upgrades at Sewage PumpStations	Р	I&E	325	325	275	-	-	925	0.4%	
DWS-932 Large Sewer Improvements: Riverdale & Rosedale	Р	I&E/Bond	4,400	400	-	-	-	4,800	2.3%	
DWS-933 Corktown Sewer	С	I&E			-	-	-	-	0.0%	
DWS-937 Sewer Replacement	N	DWRF/I&E	8,000	7,600	-	-	-	15,600	7.4%	
<b>DWS-938</b> Sewer Condition assessments throughout City (DWS-909)	N	DWRF/I&E	2,250	2,250				4,500	2.1%	
DWS-939 Sewer Condition Assessments High Priority	N	DWRF/I&E	2,250	2,250				4,500	2.1%	
Sewer Program Allowances	N	I&E	-	2,000	12,000	14,000	14,000	42,000	20.0%	
<b>CS-1812</b> Professional Engineering and Construction Services for Capital Improvement Program Management Organization	Α	I&E/ Bond	2,795		-	-	-	2,795	1.3%	
DWS-902 Repair of Pavement (break repair)	Α	I&E	75	-	-	-	-	75	0.0%	
DWS-904 Repair of Lawns (break repair)	Α	I&E	338	-	-	-	-	338	0.2%	
<b>DWS-919</b> (replace DWS-902)	N	I&E	1,200	1,200	-	-	-	2,400	1.1%	
Repair and Maintenance Allowance	N	I&E			1,000	1,000	1,000	3,000	1.4%	
CS-1921 Watermain/Sewer Design	N	I&E	1,000	1,000	1,000	-	-	3,000	1.4%	
CS-1923 Third Party Inspection (Water & Sewer)	N	I&E	750	750	750	-	-	2,250	1.1%	
CS-1522 Green Infrastructure Program Management	С	I&E	<b>Y</b> -	-	-	-	-	-	0.0%	
PC-799 Crowell Rec Center and EcoSite Modifications	С	I&E	3	-	-	-	-	3	0.0%	
PC-808 West Warren (Constance at Rouge Park/Tireman Sawyer PH III)	N	I&E	10,040	7,650	6,280	3,995	995	28,960	13.8%	
PC-808 Sewer Rehabilitation (Non GSI)	N	I&E	1,500	1,500				3,000	1.4%	
PC-801A Oakman Blvd	Α	I&E/ Bond	20	20	20	-	-	60	0.0%	
PC-800 O'Shea Park	c	I&E	10	-	-	-	-	10	0.0%	
PC-806 Charles H. Wright Academy	N	I&E	687	45	38	-	-	770	0.4%	
North Rosedale (Edinborough)	N	I&E	3	3	-	-	-	6	0.0%	
Capital Partnership Program	Р	I&E	5	-	-	-	-	5	0.0%	
Chandler Park Drive (CIPMP)	N	I&E	5	5	5	-	-	15	0.0%	
Green Stormwater Infrastructure Construction Allowance	N	I&E	-	-	-	5,000	5,000	10,000	4.8%	
CS-1884 Green Infrastructure Program Management	Р	I&E	2,500	2,500	2,500	1,000	1,000	9,500	4.5%	
Vehicle, Heavy Equipment, and Equipment Purchases	N	I&E	1,335	1,500	1,500	1,500	1,500	7,335	3.5%	
Information Technology	N	I&E	1,890	1,618	750	750	750	5,757	2.7%	
Facility Improvement Allowance	N	I&E	3,761	1,000	1,000	1,000	1,000	7,761	3.7%	
		TOTALS	73,083	49,566	34,118	28,245	25,245	210,257	100.0%	
								_		

DRAFT April 7, 2021 III-0



# **Information Technology**

Descriptions	Туре	<u> </u>		2021-22				
	Security							
DWS-912 Video Security System Upgrades	Software	Addition	\$	240,000				
Customer Service								
CS-1917 EnQuesta Upgrade	Software	Software Maintenance	\$	200,000				
	Operations							
Collaboration Software for Drainage &								
Records Management	Software	New Software Implementation	\$	190,000				
DWS-928 GPS for vehicles	Hardware/Equipment	New Hardware/Equipment Implementation	\$	564,000				
Misc. Equipment for AssetWorks	Hardware/Equipment	New Hardware/Equipment Implementation	\$	50,000				
Itron Replacement (staffing support)	Other IT Implementation	CIP IT STAFFING	\$	600,000				
CS-1952 Oracle Supply chain Management	Other IT Implementation	New Other IT Implementation Implementation	\$	800,000				
Info	rmation Technology							
Desktops	Hardware/Equipment	Hardware	\$	50,000				
Laptop Charging Stations	Hardware/Equipment	Hardware	\$	5,000				
Laptops	Hardware/Equipment	Hardware	\$	10,000				
Rugged Tablets/Laptops	Hardware/Equipment	Hardware	\$	20,000				
Tablets	Hardware/Equipment	Hardware	\$	50,000				
Low Voltage Wiring	Hardware/Equipment	New Hardware/Equipment Implementation	\$	200,000				
Phone System Migration to Avaya	Hardware/Equipment	New Hardware/Equipment Implementation	\$	20,000				
Printers	Hardware/Equipment	Hardware	\$	30,000				
Cityworks/AssetWorks/Records Implement	Other IT Implementation	New Other IT Implementation Implementation	\$	400,000				
GIS Update As-Built Drawing Upgrades	Other IT Implementation	New Other IT Implementation Implementation	\$	350,000				
Total			\$	3,779,000				

DRAFT April 7, 2021 III-1



# Vehicle, Heavy Equipment, and Equipment

Descriptions	Туре	QТY	Estimated Unit Cost	2021-22
Meter Operations			45,000	
F-350 Super Duty	Truck	1	45,000	45,000
<b>Field Services Operations</b>			1,935,000	
F150	Truck	6	45,000	270,000
F-450 Super Duty	Utility Truck	3	125,000	375,000
F-550 Super Duty	Utility Truck	5	130,000	650,000
5-Yard Dump-Salt Truck	Dump Truck	1	250,000	250,000
Mini-Excavator	Backhoe	2	150,000	300,000
Trailers for Mini Excavator	Trailer	2	30,000	60,000
Golf Cart	Vehicle	2	15,000	30,000
Fleet Operations			690,000	
SUV	Vehicle	5	32,000	160,000
Pool Vehicles	Vehicle	5	35,000	175,000
Golf Cart	Vehicle	2	15,000	30,000
F150	Truck	5	45,000	225,000
Passenger Vehicles	Vehicle	2	25,000	50,000
Confined Space Tripod	Equipment	2	12,500	25,000
Tampers/Compactors	Equipment	2	5,000	10,000
Underground Locators	Equipment	2	7,500	15,000
Total				2,670,000

DRAFT April 7, 2021 III-2



# **FY 2022 Facility Improvements**

Descriptions	Туре	QTY	Unit Cost		2021-22					
Roofing										
CSF/West/MOB	Roof replacement				3,000,000					
Heating Units										
CSF	HVAC Units	10	150,000		500,000					
West Payment	HVAC Rooftop Unit Replacement	2	15,000		30,000					
MOB	Steam Improvements				15,000					
MOB	Heat Improvement - Car Elevator area				36,000					
Misc. HVAC Improvements	Auto Garage - Extra large Fans	6	20,000		120,000					
Garage Door Replacement										
DWS-926 Overhead Dooes CSF/ West Yard	Fabric Door Replacement	10	25,000		200,000					
Interior Improvements										
Build Out	Interior Space Improvements				300,000					
DWS-914 Flooring	Interior West Yard	10	100,000		250,000					
Flooring	Exterior West Yard				150,000					
2nd Floor Admin-Buildout	Design/Feasibility				50,000					
DWS-927 Bathroom Improvements (Covid)	Design/Feasibility				150,000					
Parking Lot Improvements										
LED Lights	Yards/Garage				200,000					
Gate Operator	CSF & West Yard				20,000					
Detroit Building Authority (DBA)	Consolidation, Renovations & Im	proveme	ents		2,500,000					
Total				\$	7,521,000					



# IV. APPENDICES

**APPENDIX A - PROJECT DESCRIPTIONS** 

APPENDIX B - MAPS OF CIP PROJECT BY COUNCIL DISTRICT

APPENDIX C - STREET TABLE OF CIP PROJECTS



# **APPENDIX A – PROJECT DESCRIPTIONS**



# **WS-703 Water Main Replacement**

Status: Closed

Significance: Water main replacement

**Location:** Various

**Scope of Work:** Water main replacement at various locations in Detroit's west side. The work includes Oakman Blvd from Grand River to West Chicago, a length of residential water main adjacent to the St. John Hospital at McNichols and Schaefer, water main along Outer Drive from Grandville eastward through Southfield Freeway, Greenfield, and ending at Schaefer (Wayne County jurisdiction), Lahser from Seven Mile to Eight mile (Wayne County jurisdiction), and the water main along Outer Drive South of Plymouth adjacent to Rouge Park (Wayne County jurisdiction). Duration: 730 Calendar Days.

Street	Street Limit 1	Street Limit 2
W. Outer Drive	Plymouth	W. Chicago
W. Outer Drive	Whitcomb	Schaefer (North)
W. Outer Drive	Whitcomb	Schaefer (South)
W. Outer Drive	Rutherford	Winthrop (North)
W. Outer Drive	McNichols	Southfield (South)
W. Outer Drive	Southfield	Ferguson (North)
W. Outer Drive	Southfield	Ferguson (South)
W. Outer Drive	McNichols	Southfield (North)
W. Outer Drive	Greenfield	Whitcomb (South)
Stansbury	McNichols	Ardmore
Berg	Vassar	Leewin
Lahser	Seven Mile	Eight Mile
Oakman	Joy	Grand River
Algonac	Lappin	Manning

### **Project Cost Estimates**

					Total	Proj	ected Expe	enditures	by Fiscal Y	'ear
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	Closed	С	8/28/2017	12/31/2019	\$7,482,000					

# WS-704 Water Main Replacement – along Outerdrive

Status: Closed

**Significance:** Water main replacement along Outer Drive

**Location:** Outer Drive W, Vassar to Livernois

**Scope of Work:** Water main replacement along Outer Drive (Wayne County jurisdiction) from Vassar (north of Seven Mile and east of Schaefer) eastbound through Wyoming and ending at Livernois. Twenty thousand feet of mostly eight-inch water main (and 500 hundred feet of twelve- inch water main) replaced along both sides of Outer Drive. Duration: 730 Calendar Days.



# Project Cost Estimates

					Total Estimated Cost	Projected Expenditures by Fiscal Year						
System	Status	Туре	Start Date	Finish Date		2021-22	2022-23	2023-24	2024-25	2025-26		
Water	Closed	С	2/5/2018	2/5/2020	\$9,350,000							

Street	Street Limit 1	Street Limit 2
--------	----------------	----------------

#### North Side & South Side

Outer Drive	Ward St	Sorrento St		
Outer Drive	Sorrento St	Steel St		
Outer Drive	Steel St	Appoline St		
Outer Drive	Appoline St	Meyers Rd		
Outer Drive	Meyers Rd	Manor St		
Outer Drive	Manor St	Monte Vista St		
Outer Drive	Monte Vista St	Pinehurst St		
Outer Drive	Pinehurst St	Mendota St		
Outer Drive	Mendota St	Birwood St		
Outer Drive	Birwood St	Griggs St		
Outer Drive	Griggs St	Hene St		
Outer Drive	Hene St	Washburn St		
Outer Drive	Washburn St	Wyoming Ave		
Outer Drive	Wyoming Ave	Cranbrook Ave		
Outer Drive	Cranbrook Ave	Cherrylawn St		
Outer Drive	Cherrylawn St	Northlawn St		
Outer Drive	Northlawn St	Roselawn St		
Outer Drive	Roselawn St	Greenlawn St		
Outer Drive	Greenlawn St	Woodingham St		
Outer Drive	Woodingham St	Santa Barbara St		
Outer Drive	Santa Barbara St	Pennigton St		
Outer Drive	Pennigton St	San Juan Dr		
Outer Drive	San Juan Dr	Prairie St		
Outer Drive	Prairie St	Monica St		
Outer Drive	Monica St	Santa Rosa Dr		
Outer Drive	Santa Rosa Dr	Santa Rosa Dr		
Outer Drive	Santa Rosa Dr	Stoepel St		
Outer Drive	Stoepel St	Livernois Ave		

# WS-705 Water Main Replacement – Eastside and Westside, Select Locations

Status: Closed

**Significance:** Water main replacement at various locations in Detroit's East and West side.

**Location:** Multiple

**Scope of Work:** Residential water main replacement at various locations in Detroit's east and west sides. On the west side, water main replacement work is targeted for multiple streets in the Hubbell-Lyndon Neighborhood and Whitcomb from the Winship neighborhood. On the east side, replacement water main will be installed at various location in the Outer Drive-Hayes neighborhood and also in Yorkshire Woods, Denby, and Moross-Morang. Duration: 730 Calendar Days.

Street	Street Limit 1	Street Limit 2
Robson	<b>Grand River</b>	Chalfonte
Strathmoor	Vassar	Eight Mile
Marlowe	<b>Grand River</b>	Chalfonte
Mark Twain	Fenkell	Lyndon
Ardmore	Intervale	Lyndon
Whitcomb	Outer Drive	Curtis
Mckinney	Grayton	Morang
Britain	Cadieux	Mckinney
Nottingham	Berkshire	Whittier
Lanark	Morang	Morros
Prevost	Pembroke	Seven Mile
Rutherford	Pembroke	Seven Mile
Whitehill	Grayton	Morang
Riad	Morang	Moross
Parkgrove	Morang	Kelly

### **Project Cost Estimates**

					Total	Projected Expenditures by Fiscal Year					
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26	
Water	Closed	С	8/13/2018	12/31/2020	\$12,839,000						

# WS-706 Water Main Replacement Wayne Co. Roads

Status: Closed

Significance: Replace existing water main along roadway within Detroit.

**Location:** Various

Street	Street Limit 1	Street Limit 2
West Warren Ave	Parkland	Heyden
Tireman	Greenfield	Hubbell
Robson	Curtis	Seven Mile
Stansbury	Outer Drive	Curtis
Beaverland	Sawyer	Tireman
East Outer Drive	Dequindre	Conley
McNichols	Schaefer	James Couzens

Scope of Work: Replacement of existing water main along mostly Wayne County roadway within Detroit and a few Detroit residential streets. The Wayne County streets are Tireman from Greenfield to Lodge (piping along the Detroit side of the Detroit/Dearborn municipal line), Warren Avenue from Parkland to Heyden (west side), Outer Drive from Dequindre to Mound (east side), and McNichols from Lodge to Schaefer (west side). The residential streets are a reach of Beaverland (north of Warren and west of Rouge Park), Stansbury (north of Outer Drive, west of Lodge), and Robson (south of Seven Mile and East of Greenfield). The overall work is replacement of 26,400 LF of mostly eight-inch and some twelve and sixteen-inch water main. Duration: 730 Calendar Days.

### **Project Cost Estimates**

					Total		Projecte	d Expenditu	res by Fisc	al Year
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	Closed	С	11/5/2018	6/31/2021	\$10,294,000					

# WS-707 Water Main Replacement – Select Streets Across Detroit

Status: Closed

Significance: Water main replacement in the MDOT jurisdiction

**Location:** Various

**Scope of Work:** Work includes Outer Drive north of Mack (Wayne County jurisdiction, east side), a residential street in Warrendale, four locations in northwest Detroit, and a pair of streets in central

Detroit. Up to 20,000 LF of mostly eight-inch DI water main including two lengths of twelve inch DI main are replacing the existing pipe.

Duration: 730 Calendar Days.

### **Project Cost Estimates**

					Total	Projected Expenditures by Fiscal Year						
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-2	22	2022-23	2023-24	2024-25	2025-26	
Water	Active	С	4/15/19	6/30/21	\$15,982,000							

This is a drinking water revolving fund project.

Street	Street Limit 1	Street Limit 2
Pembroke Ave	Lodge Fwy	Biltmore Street
Fullerton Ave	Dexter Avenue	Petoskey Street
E Outer Dr	Waveney Ave	Wallingford St
Brace street	Warren Ave	Paul Ave
Coyle street	Fenkell ave	Grand River Ave
Codding street	Grand River Ave	Margareta Street
Margareta street	Codding Ave	Shiawassee Street
Whitcomb street	Pembroke Ave	Vassar Dr

#### CIP#1322,

# **WS-710 Water Main Replacement**

Status: Active

**Significance:** Replacement of existing 8" through 12" Water main with 32,780 LF of 8" through 12" Ductile Iron Water Main along various streets of Wayne County right-of-way

Location: Schoolcraft, Five Points, West Chicago, Warren, Kelly Road, and Chandler Park Drive

**Driver:** Water main breaks are a frequent occurrence and they constitute a drain on the DWSD resources necessary to address these breaks, often times during inclement weather conditions. Water main breaks can also increase the potential public health risk from cross-connection contamination (bacteriological and/or chemical) resulting from reduced pressure or depressurized water mains during the repair.

**Scope of Work:** Replacement of 31,902 LF of 8" and 479 ft of 12" pipe with ductile iron water main and installed via trenching/open cut at select locations of Schoolcraft, Five Points, West Chicago, Warren Avenue, Chandler Park Drive, and Kelly Road. Includes lead service line replacements.

**Challenges:** Minimize disruption in neighborhood

### **Project Cost Estimates**

System		Туре	Start Date	Finish Date	Total Estimated Cost	Projected Expenditures by Fiscal Year				
	Status					2021-22	2022-23	2023-24	2024-25	2025-26
Water	Active	С	7/27/2020	7/26/2022	\$9,126,360	\$1,000,000	\$100,000			

This is a drinking water revolving funded project

# **WS-711 Water Main Replacement**

Status: Active

**Significance**: Replacement of existing six, eight, twelve-inch, and sixteen-inch water main including Gate Valves, Fire Hydrants, existing Lead (Pb) water services.

Location: Various across Detroit

**Driver:** Due to the age of these pipes, water main breaks are a constant occurrence and they constitute a drain on the DWSD resources necessary to address these breaks, often times during inclement weather conditions. Water main breaks can also increase the potential public health risk from cross-connection contamination (bacteriological and/or chemical) resulting from reduced pressure or depressurized water mains during the repair.

**Scope of Work:** Replacement of 41,079 LF of 8" to 16" water main with ductile iron pipe placed via trenching/open cut at various locations on E. Jefferson, Greenfield Road, Greenview, West Parkway, and the Northbound Southfield Service Drive including lead service line replacements.

**Challenges:** Minimizing disruption to neighborhoods.

### **Project Cost Estimates**

System S		Туре	Start Date	Finish Date	Total Estimated Cost	Projected Expenditures by Fiscal Year				
	Status					2021-22	2022-23	2023-24	2024-25	2025-26
Water	Active	С	7/27/2020	7/22/2022	\$12,978,108	\$4,200,000	\$1,000,000			

This is a drinking water revolving funded project

# WS-712 Cornerstone Village Water (46,000 LF)

Status: Active

Significance: In-place rehabilitation/repair of existing water mains and associated assets

**Locations:** Cornerstone Village

Driver: Renew and rehabilitate Detroit infrastructure and neighborhoods based on CIPMO pilot study project

**Scope of Work:** Replacement or lining of approximately 46,000 linear feet of existing six, eight, twelve and sixteen-inch water main including gate valves, hydrants and replacement approximately 605 lead service lines. The project has an expected duration of 442 calendar days.

Challenges: Minimizing disruption to neighborhoods-

### **Project Cost Estimates:**

					Total	Projected Expenditures by Fiscal Year					
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26	
Water	Active	С	12/2/2019	6/23/2022	\$18,630,333	\$7,630,000	\$3,500,000				

# **WS-713 Water Main Replacement - Jefferson Chalmers**

Status: New

Significance: Water main replacement and rehabilitation within Jefferson Chalmers

Locations: Various streets within the Jefferson-Chalmers neighborhood of E. Detroit

**Driver:** 

**Scope of Work:** Replacement or lining of existing water mains including gate valves, hydrants and replacement lead service lines. 121,000 LF of water main was assessed in 2018 with design work across 2019. The work is estimated as follows:

Pipe Bursting: 11,650 LF	DI pipe installation via trenching/open cut: 7,750 LF	Project Total: 36,730 LF
Horizontal Directional Drilling: 15,880 LF	Lining of existing 8-inch pipe: 1,450 LF	

The work also includes three canal crossings either as a HDD or Jack & Bore.

### **Challenges:**

### **Project Cost Estimates**

		Status Type Start Date Finish Date			Total	Projected Expenditures by Fiscal Year					
System	Status		Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26		
Water	New	D			\$15,000,000	\$7,500,000	\$7,500,000				

This is a drinking water revolving funded project

Expenditures listed in the cost table are from the FY spreadsheets downloaded to E-Builder in Nov 2019.

# WS-714 Water Main Replacement - MDOT - Michigan Dept of Transportation (Grand River streetscape)

Street Limit 1 Street Limit 2 Street Grand River North Fenkell Evergreen Grand River South Fenkell Evergreen Grand River North Evergreen W. McNichols W. McNichols Grand River South Evergreen Grand River North W. McNichols Berg Grand River South | W. McNichols Berg

Status: Closed

Significance: Water main work along Grand River Avenue that is part of the MDOT streetscape work.

Locations: Grand River between Fenkell Ave to Marene Street

**Scope of Work:** A total of 25,100 LF of eight thru sixteen inch DIWM is replacing existing six through sixteen-inch water main along both sides of Grand River from Fenkell Avenue to Marene Street just west of Lahser. The streetscape and water main work started in August 2019; water mains from the eastern limit of the work near Fenkell westward to Evergreen are complete. Remaining water main work will be completed NLT November 2020.

Challenges: This project is coordinated with MDOT in conjunction with their streetscape project along Grand River.

### **Project Cost Estimates:**

System	Status	Туре	Start Date	Finish Date	Total Estimated Cost	Projected Expenditures by Fiscal Year				
						2021-22	2022-23	2023-24	2024-25	2025-26
Water	Closed	С	7/24/2019	12/31/2020	\$8,609,000					

This is a drinking water revolving fund project.

# WS-715 Watermain replacements West Side Neighborhoods - Riverdale, Minock Park, Miller Grove and Rosedale

Status: New

Significance: New water mains and associated infrastructures will enhance the integrity of DWSD's water systems and ensure quality service to its customers

Locations: Various locations within the neighborhoods of Riverdale, Minock Park, Miller Grove, and Rosedale Park

Driver: The extensive history of Water Main leaks and breaks that have also exceeded their intended service life.

**Scope of Work:** Replacement or lining of approximately existing water main including gate valves, hydrants and replacement lead service lines. 591,000 LF of water main across all four neighborhoods have been condition assessed. The work across the neighborhoods are as follows:

Lining of Existing 8-inch mains: 4,400 LF	Horizontal Directional Drilling (HDD): 5,925 LF	Project total: 25,485 LF
Pipe Burst: 8,700 LF	Ductile Iron Pipe Installation via trenching/open cut: 6,460 LF	

## **Challenges:**

### **Project Cost Estimates:**

					Total	Projected Expenditures by Fiscal Year					
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26	
Water	New	С	-	-	\$16,900,000	\$6,900,000	\$7,000,000	\$3,000,000			

This is a drinking water revolving funded project

## WS-718 Watermain replacements for New Center Commons and Virginia Park

Status: New

Significance:

Locations: Various Locations within neighborhoods of New Center Commons and Virginia Park

**Driver:** 

**Scope of Work:** Replacement of approximately 9,516 linear feet of existing six, eight, twelve and sixteen-inch water main including gate valves, fire hydrants, approximately 1,575 linear feet of existing lead services, and all appurtenances required to complete the work. The Work across both neighborhoods are as follows:

Lining of Existing mains: none	Horizontal Directional Drilling (HDD): 5,580 LF	Project total: 9,516 LF
Pipe Burst: 1,272 LF	Ductile Iron Pipe Installation via trenching/open cut: 2,664 LF	

FYI: The scope of this project is smaller than a typical DWSD project, so has a duration of only one year.

## **Challenges:**

#### **Project Cost Estimates:**

					Total	Projected Expenditures by Fiscal Year					
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26	
Water	New	С	12/9/2020	12/8/2021	\$4,290,000	\$2,300,000					

This is a drinking water revolving funded project

# WS-720 Watermain Replacements – Various Streets

Status: New

Significance:

Location: Evergreen - Outer Drive, Grand River - St. Mary's, Grand River - I96, Warrendale, and Franklin Park neighborhoods of

Detroit

**Driver:** 

**Scope of Work:** Replacement of approximately 26,932 linear feet of existing six, eight, and twelve-inch water main including gate valves, fire hydrants, approximately 246 Lead (Pb) services at 14,106 linear feet in total, and all appurtenances required to complete the work. The Work across the neighborhoods is as follows:

Lining of Existing mains: none	Horizontal Directional Drilling (HDD): 14,906 LF	Project total: 26,932 LF
Pipe Burst: 4,857 LF	Ductile Iron Pipe Installation via trenching/open cut: 7,169 LF	

## **Challenges:**

					Total	Projected Expenditures by Fiscal Year						
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26		
Water	New	С	-	-	\$12,100,000	\$3,100,000	\$6,000,000	\$3,000,000				

# WS-721: Lead Service Line Replacement, Various Locations Throughout the City

Status: New

Significance: The City of Detroit has an estimated 80,000 + Lead (Pb) water services active within the municipal water system. Given the potential negative health impacts to water system customers, DWSD has been undertaking efforts in the replacement of these services. Per EPA and MI-EGLE requirements, Lead services are replaced from the water main all the way to the customer meter within their property (residence, commercial space, other). Normally, Lead replacements are integrated into water main replacement capital work, but not all water mains can be replaced over the next handful of years to capture all the outstanding Lead services. While the Lead services are expected to be within the older portions of Detroit, realistically, they can be located in any neighborhood, thus the scope of this project will be across the entirety of the Detroit water system.

**Locations:** Various

**Driver:** 

**Scope of Work:** Replacement of Lead (Pb) water services of two-inches and less with Type K soft copper. Up to 2000 services will be replaced across several years with a combination of excavation and directional boring to minimize impacts upon customer properties.

## **Challenges:**

					Total	P	Projected Expenditures by Fiscal Year				
System	Status	Type	Start Date	Finish Date	Éstimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26	
Water	New	С	August 2021	August 2023	\$11,000,000	\$6,000,000	\$5,000,000				

## **WS-723 Lead Service Line Replacement**

Status: New

Significance:

Location: Various individual addresses across Detroit

**Driver:** 

**Scope of Work:** Replacement of Lead (Pb) water service lines from the existing water main to the customer meter. The water services will be placed through directional boring so as to minimize disruption to the private property and keep excavation work limited to the green space between the sidewalk and nearby road curb. This work will be expressly within the properties of the Land Bank, Bridging Neighborhoods and other City of Detroit agencies that deal with property ownership, transfer, and management. These offices will request work be done by DWSD and the City Agencies will reimburse DWSD through MOU's established prior to work.

#### **Challenges:**

					Total		rojected Ex	ojected Expenditures by Fiscal Year			
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26	
Water	New	С	-	-	\$1,000,,000	\$800,000	\$200,000				

# WS-725 Watermain Replacements – Medical Ctr, Cultural Ctr, & Midtown 30,000LF

Status: New

Significance:

Location: Select water main replacement in the Midtown, Cultural Center, and Medical Center neighborhoods of Detroit

**Driver:** 

**Scope of Work:** Water main replacement of approximately 63,000 LF of water main identified through field data gleaned through condition assessment work and subsequent evaluation of the networks through the DWSD Risk Assessment model.

#### **Challenges:**

					Total		Projected Expenditures by Fiscal Year				
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-2	3	2023-24	2024-25	2025-26
Water	New	С	-	-	\$14,000,000		\$4,000	,000	\$5,000,000	\$5,000,000	

#### CIP#O&M

## WS-702 Repair & Replacement of Water Mains

**Status:** Active

**Significance:** This is a hybrid contract with both repair and replacement work. The repair work is intended for emergency water main replacement without construction drawings.

**Location:** Various

**Driver:** During certain periods of the year, the DWSD experiences a significant increase in the number of water main breaks and leaks. This contract will supplement the DWSD maintenance forces in repair and replacements.

**Scope of Work:** Water main repair and replacement as-needed in the city of Detroit including but not limited to the replacement and installation of new water mains, water services, hydrants, valves, gate wells, gate boxes, thrust blocks, and other water main related work.

**Challenges:** Carefully exposing the failed sections of water main. Minimizing the disturbances to customers. Minimizing the interruption of water services to customers.

		_			Total	Pro	Fiscal Year	•		
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	Active	С	2/1/2018	6/30/2021	\$17,429,100					

# **WS-708 Repair of Water Mains**

Status: Active

Significance: Repair of various sized water main due to significant increase in number of water main breaks and leaks.

**Location:** Various locations

**Driver:** Number of water main breaks and leaks in the water distribution system during critical time periods.

**Scope of Work:** Locate, expose and repair various sized water main breaks and leaks on existing water mains (up to 16"), services and the repair and replacement of hydrants, valves, stop boxes, road gate boxes and other appurtenances

**Challenges:** Minimizing disruptions to neighborhoods.

					Total		Projected Expenditures by Fiscal Year						
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26			
Water	Active	С	10/22/2018	6/30/2021	\$8,002,800								

## WS-717 Repair & Replacements of Water Main (WS-702)

Status: Active

**Significance:** This is a hybrid contract with both repair and replacement work. The repair work is intended for emergency watermain replacement without construction drawings.

**Location:** Various

**Driver:** During certain periods of the year, the DWSD experiences a significant increase in the number of water main breaks and leaks. This contract will supplement the DWSD maintenance forces in repair and replacements.

**Scope of Work:** Water main repair and replacement as-needed throughout the city of Detroit including but not limited to the replacement and installation of new water mains, water services, hydrants, valves, gate wells, gate boxes, thrust blocks, and other water main related work.

**Challenges:** Carefully exposing the failed sections of water main. Minimizing the disturbances to customers. Minimizing the interruption of water services to customers.

				To	Total	Projected Expenditures by Fiscal Year					
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26	
Water	New	С			\$14,000,000	\$4,000,000	\$3,000,000	\$3,000,000	\$3,000,000		

# WS-719 Repair of Water Mains (WS-708)

Status: Active

Significance: Repair of various sized water main due to significant increase in number of water main breaks and leaks.

**Location:** Various locations

Driver: Number of water main breaks and leaks in the water distribution system during critical time periods.

**Scope of Work:** Locate, expose and repair various sized water main breaks and leaks on existing water mains (up to 16"), services and the repair and replacement of hydrants, valves, stop boxes, road gate boxes and other appurtenances

**Challenges:** Minimizing disruptions to neighborhoods.

					Total		<b>Projected Ex</b>	penditures b	y Fiscal Year	'
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	New	С			\$4,000,000	-	-	\$2,000,000	\$2,000,000	

#### CIP# O&M

# **DWS-902 Repair of Pavement (break repair)**

**Status:** Active

Significance: To repair pavement, sidewalks, driveways, and curb cuts in various streets throughout the City of Detroit.

**Location:** Various

**Driver:** Work is done as a resulting of DWSD emergency maintenance and repair work.

**Scope of Work:** The work consists of trimming, removing, and replacing concrete sidewalks, driveways, and curbs. The object of the proposed contract consists of but is not limited to the removal of approximately 202,500 square yards of pavement cuts or patches; the replacement of 42,000 square yards of concrete, and 150,000 square yards of high early strength no slump concrete base. The removal and replacement of 360,000 square feet of sidewalk; 120,000 square feet of driveway, and 50,000 linear curb at various locations throughout the City of Detroit.

### **Challenges:**

					Total	Pro	Projected Expenditures by Fiscal Year				
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26	
Water	Active	С	8/8/2017	6/30/2021	\$20,129,000	\$1,920,000					
Sewer	Active	С	8/8/2017	6/30/2021	\$3,552,000	\$75,000					

#### CIP# O&M

## **DWS-904 Repair of Lawns (break repair)**

**Status:** Active

**Significance:** To repair lawns, berms, and trees damaged due to maintenance of water system and green stormwater infrastructures vegetation management and irrigation services.

**Location:** Various

**Driver:** Work is done as a resulting of DWSD emergency maintenance and repair work, includes green infrastructure maintenance.

**Scope of Work:** The work consists of removing undesirable debris in existing soil, grading/leveling soil and replacing seeding with straw or placing sods. DWSD is a co-permittee with Great Lakes Water Authority (GLWA) of NPDES permit. DWSD and GLWA are jointly responsible for developing and implementing the Alternative Rouge River Combined Sewer Overflow (CSO) Control Program.

This work will include excavating and grading the damaged areas. The work will also include maintenance of green stormwater infrastructure vegetation sites.

#### **Challenges:**

					Total	Projected Expenditures by Fiscal Year						
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26		
Water	Active	С	5/1/2018	4/30/2021	\$1,595,000	\$1,500,000						
Sewer	Active	С	5/1/2018	4/30/2021	\$1,063,000	\$338,000						

# DWS-919 (Replace DWS-902)

**Status:** Active

**Significance:** To repair pavement, sidewalks, driveways, and curb cuts in various streets throughout the City of Detroit.

**Location:** Various

**Driver:** Work is done as a resulting of DWSD emergency maintenance and repair work.

**Scope of Work:** The work consists of trimming, removing, and replacing concrete sidewalks, driveways, and curbs. The object of the proposed contract consists of but is not limited to the removal of approximately 202,500 square yards of pavement cuts or patches; the replacement of 42,000 square yards of concrete, and 150,000 square yards of high early strength no slump concrete base. The removal and replacement of 360,000 square feet of sidewalk; 120,000 square feet of driveway, and 50,000 linear curb at various locations throughout the City of Detroit.

### **Challenges:**

			Start	Finish	Total	P	rojected Exp	enditures by	Fiscal Year	
System	Status	Туре	Date Date Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26		
Water	New	С			\$20,400,000	\$4,080,000	\$6,800,000	\$6,800,000	\$2,720,000	
Sewer	New	С			\$2,400,000	\$1,200,000	\$1,200,000			

# PC-808 West Warren (Constance at Rouge Park/Tireman Sawyer PH III)

Status: New

Significance: Reduce volume to URT (outfalls 059-69, 072-075, 077, 079)

**Location:** Farwest Neighborhood; Constance & Parkland Street; Rouge Park


Driver: DWSD NPDES Permit No. MI0022802

**Scope of Work:** Provide the outlet for the Constance storm sewer constructed in Phase I as a large bioretention basin envisioned as both stormwater treatment and a park amenity constructed within the park to provide detention and water quality treatment. Project also includes a large open channel practice in the southern part of Rouge Park for the par41\$tial sewer separation for the area tributary to the Warren Outfall.

**Challenges:** Coordination with Friends of the Rouge for an acceptable GSI design and MDEQ approvals.







## CS-1909A Water Main Condition Assessment Services Throughout the City of Detorit

Status: New

**Significance:** Hydrant flow test (approx. 620) C-factor tests (approx. 210), valve exercising (approx. 5,907), and leak detection test (approximately 1,234,407 LF).

**Location:** Various

Driver:

**Scope of Work:** The project will include evaluating the condition of approx. 1,230,000 lineal feet of pipes, all valves and certain hydrants within fifteen Detroit neighborhoods; and evaluating the condition approximately 351,671 lineal feet of pipes, valves and hydrants at various locations throughout the City of Detroit. The pipe test section will range in length, size and material including the following: 6-inch, 8-inch, and 12-inch diameter asbestos cement (AC), cast iron, concrete, ductile iron, high density polyethylene(HDPE), and steel material. RB: FYI, there is no PVC piping within any portion of the Detroit water system.

### **Challenges:**

					Total	ı	Projected Ex	penditures b	y Fiscal Year	
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	New	S	1/22/2021	9/24/2021	\$481,909	\$250,000				

## **CS-1921 Watermain/Sewer Design**

Status: New

**Significance:** Task Order as-needed design services to improve the water and sewer piping system within the City of Detroit. Improved contract documents such as Boiler Plate (in the EJCDC format) and technical specifications in the FormSpec style of specifications.

**Location:** Various

**Driver:** This contract will phase out the condition assessment, design and construction assistance work currently provided by CS-1812, CIPMO contract as needed.

**Scope of Work:** This project consists of water and sewer design tasks including, but not limited to, civil, structural, architectural, geotechnical, hydraulics, GIS and other services as identified in the individual Task Orders. Owner will evaluate and select qualified firms or project teams to perform water and sewer professional engineering services on a Task Order basis for a Contract duration of three (3) years with the payable Contract value not to exceed two million dollars (\$2,000,000.00) per fiscal year.

Challenges: Continue defined capital improvement programs for water main and sewer improvements.

				Total		Projected Expenditures by Fiscal Year						
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26		
Water	New	D			\$3,000,000	\$1,000,000	\$1,000,000	\$1,000,000				
Sewer	New	D			\$3,000,000	\$1,000,000	\$1,000,000	\$1,000,000				

# **CS-1923A Third Party Inspection (Water & Sewer)**

Status: New

Significance: Task Order as-needed construction inspection and related services to improve the water and sewer infrastructure within the City

of Detroit

Location: All DWSD Design Contracts

**Driver:** Provide inspection services to DWSD future construction projects and transition construction inspection services from CIPMO to this

contract

**Scope of Work:** Construction Field Inspection, Field Surveying and Materials Testing by selected firms for use in future water & sewer Capital

Improvement Projects.

**Challenges:** Continue capital improvement programs for water main and sewer infrastructure improvements.

					Total	T I	rojected Exp	penditures b	y Fiscal Year	
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	New	CA			\$2,250,000	\$750,000	\$750,000	\$750,000		
Sewer	New	CA			\$2,250,000	\$750,000	\$750,000	\$750,000		

## **CS-1812 Professional Engineering and Construction Services for CIPMO**

Status: Active

Significance: Improve customer service and renew and rehabilitate Detroit's retail system infrastructure

Location: Various

**Driver:** 

**Scope of Work:** The proposed contract is a major component of the City's larger capital investment strategy designed to:

• Renew and rehabilitate Detroit infrastructure and neighborhoods;

• Reconfigure systems to reflect demographic trends and emerging urban plans;

• Re-landscape the urban environment to embrace the "greening of Detroit".

The initiation and execution of projects under this CIPMO will be prioritized to effectively and efficiently improve customer service and renew and rehabilitate Detroit's retail system infrastructure. A centerpiece of the CIP is the development of a CIP program management organization (CIPMO) with responsibility to coordinate and execute capital project planning and implementation across multiple agencies responsible for infrastructure and community development.

#### **Challenges:**

			Start Date	Finish	Total	Pro	jected Exp	enditures b	y Fiscal Yea	ır
System	Status	Туре	Start Date	Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	Active	C/CA/D/S	7/10/2017	7/9/2022	\$28,703,000	\$2,795,000				
Sewer	Active	C/CA/D/S	7/10/2017	7/9/2022	\$28,703,000	\$2,795,000				

# **CS-1925 Itron Migration – MIU Replacement**

Status: New

**Significance:** Enhanced meter reading technology to support Consumption and Billing related activities. To modernize billing practices to improve meter reading, billing efficiency and accuracy to minimize/eliminate estimated bills.

Location: Detroit Service Area

**Driver:** Warranty Replacement

**Scope of Work:** DWSD Contract CS-1925 will implement Open Way Riva Solution as a warranty replacement of the existing Water SaveSource Solution implemented back in 2007. The project scope includes removal, decommissioning and disposal of the 200W SaveSource endpoints, as well as the SaveSource collector network and the installation of RIVA endpoints, RIVA software and RIVA network. The Open Way Riva Solution provides DWSD with meter readings to accurately bill our customers.

DWSD installed MIU's on each of its customer's properties and collection towers across the city to interface with the MIU's. The MIU's collect and transmit meter reading to collection towers which then transmit the meter reading into the billing system. There are currently 210,000 customer accounts with installed MIUs. MIU's have a warrantied life of 20 years and are reaching obsolescence due to manufacturing difficulties. It is in DWSD's interest to proactively schedule replacement of its equipment to mitigate customer impact.

Challenges: Seamlessly install and integrate the new system to avoid estimated bills.

					Total	F	Projected Ex	penditures b	y Fiscal Year	
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	New	С			\$13,500,000	\$5,931,000				

# **CS-1926 Itron Migration Project Management**

Status: New

Significance: Improve the life cycle management of Riva system Assets.

**Location: Various** 

**Driver:** 

**Scope of Work:** Successfully replace the existing Water SaveSource AMR with the Riva OpenWay AMI (Advanced Metering Infrastructure) system. Integrate the Riva module system into daily operating procedures to achieve and sustain a module availability rate of 98.5% and limit out of service for reading modules to no more than 3 consecutive months. Integrate the Riva system with DWSD operations. Improve the life cycle management of Riva system assets. Leverage the capabilities of the Riva network for Internet of Things (IT) applications.

**Challenges:** 

					Total		Projected Ex	penditures k	y Fiscal Year	
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	New	CA	8/1/2020	7/31/2023	\$2,380,517	\$2,069,000				

## PC-803B AMR Skilled Trade Labor

Status: New

**Significance:** Assistance with Small Meter Installations

**Location: Citywide** 

**Driver:** Increased number of small meter installation appointments

Scope of Work: Contractual crews supporting the Meter Operations Division in installing small (less than = 2") retail water meters and meter interface units (MIUs) for automatic meter reading (AMR) throughout the City of Detroit.

## **Challenges:**

Type Status	D-Design	Start	Finish	Total Estimated	Proj	ected Expe	enditures l	y Fiscal Y	'ear	
1 7 60	Status	C-Construction	Date	Date	Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	New		4/8/2019	4/8/2022	1.884,998					

# **Water Meter Replacement Program**

Status: Active

**Significance:** This program will provide assistance with meter operations of the exchange, removal and repair of meters

**Location:** Various

			Total	Projected Expenditures by Fiscal Year							
System	Status	Туре	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26			
Water	Active	С	\$3,451,000	\$451,000	\$750,000	\$750,000	\$750,000	\$750,000			

## **Fire Hydrant Replacement Program**

Status: Active

**Significance:** To improve the level of service and sustain the progress made with the City of Detroit Insurance Service Office (ISO) 2018 assessment rating

#### Location:

**Driver:** With nearly 10% inoperable hydrants within the City at the onset of this program in 2015 and a previous level 4 ISO rating, replacement of inoperable hydrants was given priority and funding to reach national standards of 1.5% hydrant inoperability.

**Scope of Work:** With nearly 30,000 hydrants within that City that are annually inspected, DWSD needs sufficient supply of hydrants to replace and repair inoperable hydrants that are needed to maintain fire flow capability, accommodate the required wet demolition that is performed utilizing hydrant permits and prevent creating a backlog of replacing inoperable hydrants. With the efforts completed to date, DWSD and DFD can prioritize work by critical facility proximity, have institutionalized the hydrant inspection program and established a uniform database of hydrant assets.

#### **Challenges:**

			Total		Projected Ex	penditures b	y Fiscal Yea	ſ
System	Status	Type	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Water	Active		\$1,250,000	\$250,000	\$250,000	\$250,000	\$250,000	\$250,000

# **DWS-903 Inspection and Rehabilitation of Sewers City**

Status: Active

Significance: Provide as-needed inspection and in-place rehabilitation of selected sewers

**Location:** Various

**Driver:** 

**Scope of Work:** Proposed Contract No. DWS-903 is a continuation of the scope of work being performed under the existing Contract Nos. DWS-889, DWS-890, DWS-900 and DWS-901. The purpose of this contract is to provide as-needed inspection and in-place rehabilitation of selected sewers primarily using the procedures, methods and equipment of the cured-in-place pipe lining process.

The existing Detroit Water and Sewerage Department (DWSD) sewer system within the City limits (approximately 3,000 miles of sewers ranging from 8" thru 168") is generally older than ninety-years. As a result of the sewers age, they are deteriorating at a faster rate. Some are near the point of collapsing, and immediate emergency action is often required. Sewer rehabilitation services are needed to repair plugged, damaged and collapsed sewers to avoid basement flooding, and maintain the flows within the wastewater collection system.

In the last rehabilitation/lining contracts, DWSD expended approximately \$9,000,000 per year. DWSD is planning to continue the rehabilitation of sewers and anticipates spending approximately \$20,000,000 per year to provide better service to the citizens of Detroit, and meet the needs of future City development. The rehabilitation/lining process will extend the life of a sewer by at least 50 years.

### **Challenges:**

					Total		Projected Ex	penditures by	Fiscal Year	
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Active	С	12/11/2017	6/30/2021	\$65,000,000	\$7,000,000				

# DWS-907 Watermain and Sewer Rehabilitation & Replacement, North Rosedale Park

Status: Active

Significance: In-place rehabilitation/repair of existing sewers and

replacement of water mains

**Locations:** North Rosedale Park

**Driver:** Renew and rehabilitate Detroit infrastructure and neighborhoods based on CIPMO pilot study project. DWSD NPDES Permit No. MI0022802

**Scope of Work:** Replacement of approximately 17,000 LF of 8" water main, replacement of 250 lead service lines and 31,000 LF of 8" to 33" replacement and lined Sewer and construction of 150 LF of Green Stormwater Infrastructure Bioretention. Installation of turf grass bioretention in the berm along Edinborough.





**Proposed Street View** 

**Challenges:** Minimizing disruption to neighborhoods, includes improvements in backyard sewer easements. This work is to the sewer proper.

					Total		0				
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26	
Water	Active	С	12/2/2019	5/25/2022	\$7,819,000	\$5,000,000					
Sewer	Active	С	12/2/2019	5/25/2022	\$5,213,000	\$3,000,000					
Sewer (GSI)	Active	С	12/2/2019	5/25/2022	\$98,000	3,000	3,000				

# DWS-908 Sewer Rehabilitation & Replacement, Cornerstone Village

Status: Active

**Significance:** In-place rehabilitation/repair of existing sewers


**Locations:** Cornerstone Village

Driver: Renew and rehabilitate Detroit infrastructure and neighborhoods based on CIPMO pilot study project

**Scope of Work:** Rehabilitation of 42,000 LF of CIPP sewer lining, 1900 LF of trenchless point repair, 32,000 LF of sewer O&M, 550 LF of newly constructed sewer, 1,300 LF of external point repair, and 3,250 SF of Green Storm Water Infrastructure.

Challenges: Minimizing disruption to neighborhoods, includes improvements in backyard easements

		D-Design			Total		Projected E	xpenditures	by Fiscal Year	•
Type	Status	C-Const.	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Active	С	12/2/2019	12/1/2021	\$7,693,349	\$2,693,000				



# **DWS-909 Sewer Condition Assessment Services in Various Locations Throughout The City of Detroit**

Status: Closed

**Significance:** Inspection and cleaning of Existing Sewer Systems

**Locations:** Various Streets throughout Detroit


**Driver:** Assessment of Detroit infrastructure and neighborhoods

Preliminary Scope of Work: 179,660 LF of Sewer cleaning, 317,673 LF of inspection, 802 manhole inspections and 2,200 catch basins

Challenges: Minimizing disruption to neighborhoods, includes improvements in backyard easements

					Total	P	rojected Expe	nditures by	Fiscal Yea	r
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Closed	D	4/6/2020	4/5/2021	\$1,500,000					

# DWS-910 Sewer Condition Assessment Services in Hubbard Farms, Hubbard Richard, West Side Industrial, Midtown, North Corktown, and Various Streets



Status: Closed

Significance: Inspection and cleaning of Existing Sewer Systems

Locations: Hubbard Farms, Hubbard Richard, West Side Industrial, Midtown, North Corktown, and Various Streets

**Driver:** Assessment of Detroit infrastructure and neighborhoods

Scope of Work: 281,448 LF of Sewer cleaning, 714,053 LF of inspection, 2,792 manhole inspections and 2,316 catch basins

Challenges: Minimizing disruption to neighborhoods, includes improvements in backyard easements

					Total	P	rojected Ex	kpenditure	s by Fiscal Yea	r
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Closed	С	4/6/2020	4/5/2021	\$3,007,120					

# DWS-916 Sewer Improvements At Piety Hill, Virginia Park, New Center Commons, Brester Homes, and Brewster Douglass (High Priority Neighborhoods)

**Status:** Active

**Significance:** In-place rehabilitation/repair of existing sewers

**Location: Various** 

Driver: Renew and rehabilitate Detroit infrastructure and neighborhoods based on CIPMO pilot study project

**Scope of Work:** The work consists of the rehabilitation and replacement of approximately 30,815 LF of 6-inch to 75- inch sewer and manholes by external point repairs, trenchless point repairs, and CIPP lining. The work also includes approximately 18,536 LF of 6-inch to 78-inch of sewer cleaning without subsequent rehabilitation. In addition, the work includes the installation of 24 new manholes, eight new catch basins, and cleaning and repair of 76 manholes.

**Challenges:** Minimizing disruption to neighborhoods, includes improvements in backyard sewer easements. This work is to eliminate backup sewer

					Total		Projected Ex	penditures by	Fiscal Year	
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Active	С	12/16/2020	12/15/2021	\$4,732,017	\$2,600,000				

## **DWS-917 Sewer Improvement in Riverdale**

Status: New

**Significance:** Rehabilitation, replacement, and operation and maintenance interventions of buried sewer infrastructure in the Riverdale neighborhood that was identified in previous condition assessment work.

**Location: Riverdale Neighborhoods** 


**Driver:** Renew and rehabilitate Detroit infrastructure and neighborhoods based on CIPMO pilot study project

**Scope of Work:** Typical sewer pipe repair improvements will include external point repairs (EPRs), trenchless point repairs (TPRs) such as lining and patching, and full segment lining. Operation and maintenance include activities such as cleaning and cutting and grinding taps. Manhole

improvements include cleaning/flushing manholes, general spot repairs, benching and channel reconstruction, chimney reconstruction, spray lining, and replacing adjusters.

**Challenges:** Carefully exposing the failed sections of sewer. Minimizing the disturbances to customers.

					Total		Projected Ex	penditures by	Fiscal Year	
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	New	С			\$10,100,000	\$5,000,000	\$4,800,000	\$300,000		



## **DWS-918 Sewer Improvement in Rosedale**

Status: New

Significance:

**Location:** Rehabilitation, replacement, and operation and maintenance interventions of buried sewer infrastructure in the Rosedale Park neighborhood that was identified in previous condition assessment work.

Driver: Renew and rehabilitate Detroit infrastructure and neighborhoods based on CIPMO pilot study project

**Scope of Work:** Typical sewer pipe repair improvements will include external point repairs (EPRs), trenchless point repairs (TPRs) such as lining and patching, and full segment lining. Operation and maintenance include activities such as cleaning and cutting and grinding taps. Manhole improvements include cleaning/flushing manholes, general spot repairs, benching and channel reconstruction, chimney reconstruction, spray lining, and replacing adjusters.

**Challenges:** Carefully exposing the failed sections of sewer. Minimizing the disturbances to customers.

					Total		Projected Ex	penditures by	Fiscal Year	
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	New	С			\$4,900,000	\$4,450,000	\$450,000			

# **DWS-920 Inspection and Rehabiliatation of Sewers Citywide (Replace DWS-903)**

Status: New

Significance: Provide as-needed inspection, open cut repair and minimum in-place rehabilitation of failed sewers

**Location: Various Locations Throughout the City of Detroit** 

**Driver:** The existing Detroit Water and Sewerage Department (DWSD) sewer system within the City limits (approximately 3,000 miles of sewers ranging from 6" thru 168") is generally older than ninety-years. As a result of the sewers age, they are deteriorating at a faster rate. Some are near the point of collapsing, and immediate emergency action is often required. Sewer rehabilitation services are needed to repair plugged, damaged and collapsed sewers to avoid basement flooding, and maintain the flows within the wastewater collection system

**Scope of Work:** The Proposed Contract DWS-920 is the replacement for DWS-903 but will be mostly limited to as needed inspection of sewers based on customers' complaints of water-in-basement, cave-in, etc. and the providing the required open cut repair and limited sewer lining.

## **Challenges:**

					Total		Projected Ex	penditures by	Fiscal Year	
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	New	С			\$15,000,000	\$3,000,000	\$8,000,000	\$4,000,000		

# DWS-921 Electrical Monitoring Upgrades at Belle Isle, Blue Hill, Woodmere, Fischer Sewage Pump Stations









**Status:** Procurement

**Significance:** With the installation of power quality metering upgrades at the pump stations operational efficiencies may be realized and implemented.

Location: Four (4) Sewage Pump Stations owned by DWSD

Driver: The pump stations do not currently have power quality metering that communicates with a Power Management System (PMS).

**Scope of Work:** The work includes, but not necessarily limited to the removal and replacement of PP-1 at the Belle Isle Pump Station, connecting the existing PM800 meter at the Fischer Pump Station to the Ovation DCS and PMS, and furnishing and installing power quality meters at both the Blue Hill Pump Station and Woodmere Pump Station.

#### **Challenges:**

					Total		Projected Exp	penditures by	Fiscal Year	
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Procurement	С			\$600,000	\$200,000	\$200,000	\$200,000		

# DWS-926 Sewer Condition Assessments – West Village, Southwest Detroit, Michigan-Martin

**Status:** Procurement

Significance: Assessment and inventory of DWSD assets to identify areas that need repair and/or rehabilitation

Location: West Village, Southwest Detroit, Michigan-Martin and Corktown

**Driver:** Sewer condition assessment in neighborhoods

**Scope of Work:** Sewer condition assessment services in West Village, Southwest Detroit, Michigan-Martin and Corktown. Includes but is not limited to assessment of 354,145 LF of sewers and inspection of approximately 1,400 manholes in order to conduct NASSCO compliant inspections for the purpose of recording structural and service defects.

**Challenges:** Carefully exposing the failed sections of sewer. Minimizing the disturbances to customers.

					Total		Projected Exp	enditures by	Fiscal Year	
System	Status	Type	Start Date	Finish Date	Estimated 202	21-22	2022-23	2023-24	2024-25	2025-26
Sewer	Procurement	С			\$5,000,000		\$2,500,000	\$2,500,000		

# **DWS-931 Roofing Upgrades at Sewage Pump Stations**

Status: Design

Significance: Reduce infrastructure damage and stop deteriorating conditions of the pump station structure and equipment

Location: Four (4) Sewage Pump Stations owned by DWSD

**Driver:** Proposed work led by the recent condition assessment of the pump stations.

**Scope of Work:** The work includes, but not necessarily limited to removal and replacement of existing build-up, membrane, metal, and or shingle type roofs, including all accessories such as flashing, expansion joints, roof drains/conductors and sealing cap stones to prevent water from penetrating the building envelop and causing water damage to the surrounding structure.

#### **Challenges:**

					Total	Projected Expenditures by Fiscal Year				
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Design	С			\$650,000	\$325,000	\$325,000	\$275,000		

# **DWS-932 Large Sewer Improvements: Riverdale & Rosedale**

**Status:** Procurement

**Significance:** In-place rehabilitation / repair of existing sewers

**Location:** Various locations in Riverdale and Rosedale Park

**Driver:** Renew and rehabilitate Detroit infrastructure and neighborhoods based on CIPMO pilot study project.

**Scope of Work:** The rehabilitation of large diameter sewers will include man-entry walk-through inspection, internal repairs, cleaning and site restoration.

**Challenges:** Carefully exposing the failed sections of water main. Minimizing the disturbances to customers.

System	Status	Туре	Start Date	Finish Date	Total Estimated Cost		Projected Expenditures by Fiscal Year				
						2021-22	2022-23	2023-24	2024-25	2025-26	
Sewer	Procurement	С			\$4,800,000	\$4,400,000	\$400,000				

## **DWS-933 Corktown Sewer**

Status: Closed

Significance:

Location: Corktown Sewer located between 1723 Lafayette Blvd. and 1700 Fort St. Detroit, MI 48216

**Driver:** Recent discovery of 95% sewer back-up caused for the need of sewer replacement, and the need for a downstream manhole.

**Scope of Work:** The solution was to install 145 linear feet of 24-inch sewer and bulkhead then flowable fill the 5-foot sewer segment west of 11th St. A new manhole on the west end (upstream) of the new sewer was installed and a catch basin was replaced.

A full concrete sewer encasement structure with a 6-foot opening (downstream manhole) was installed in lieu of an inline connection to the 5"-0" alley sewer in vacated 11th St between Lafayette and Fort St. The manhole is needed to facilitate lining of this 5'-0" sewer segment that leads into the Detroit River Interceptor (DRI) at Jefferson Ave.

**Challenges:** DWSD permits request for sewer taps.

					Total		Projected Exp	enditures by	y Fiscal Year	
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Closed	С	7/1/2020	6/30/2021	\$172,336					

## **DWS-937 Sewer Replacement**

Status: New

**Significance:** In-Place Rehabilitation/repair of Existing Sewers

Location: Hubbard Farms, Hubbard Richard, West Side Industrial, Midtown, North Corktown, and Various Streets Throughout the City of Detroit

Driver: Renew and rehabilitate Detroit infrastructure and neighborhoods based on CIPMO pilot study project

Scope of Work: The scope will be developed from the sewer assessment performed in the neighborhoods for DWS-909/938 and DWS-910/939

Challenges: Minimizing disruption to neighborhoods, includes improvements in backyard easements

**Project Cost Estimates:** For now, the Cost Estimate is shown below. However, more accurate cost estimate will be developed after sewer assessment determines the rehabilitation needs.

					Total		Projected Ex	penditures by	Fiscal Year	
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	New	С			\$15,600,000	\$8,000,000	\$7,600,000			

# DWS-938 Sewer Condition Assessment\_throughout City (DWS-909)

Status: New

Significance: Inspection, cleaning and assessment of existing sewer systems

**Location:** Various locations throughout the City of Detroit

**Driver:** Assessment of Detroit infrastructure and neighborhoods

**Scope of Work:** Sewer cleaning in order to perform NASSCO compliant inspection of approximately using CCVT to record defects.

Challenges: Minimizing disruption to neighborhoods, includes improvements in backyard easements

					Total		Projected Ex	penditures by	Fiscal Year	
System	Status	Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	New	С			\$4,500,000	\$2,250,000	\$2,250,000			

## **DWS-939 Sewer Condition Assessment High Priority**

Status: New

**Significance:** Inspection, cleaning and assessment of existing sewer systems

Location: Hubbard Farms, Hubbard Richard, West Side Industrial, Midtown, North

Corktown, and Various Streets

**Driver:** Assessment of Detroit infrastructure and neighborhoods

**Scope of Work:** Cleaning approximately 101,788 LF of sewer in order to perform NASSCO compliant inspection of approximately 342,390 LF of

sewer using CCVT to record defects.

Challenges: Minimizing disruptions to neighborhoods, includes improvements in backyard easements

					Total		Projected Ex	penditures by	Fiscal Year	
System	Status	Туре	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	New	С			\$4,500,000	\$2,250,000	\$2,250,000			



## **CS-1522 Green Infrastructure Program Management**

Status: Closed

Significance: To study, design and develop bid documents and provide construction oversight of green infrastructure techniques and

implementation.

**Location:** Upper Rouge Tributary Area

**Driver:** DWSD NPDES Permit No. MI0022802

**Scope of Work:** To study, design and develop bid documents and provide construction oversight of green infrastructure implementation. Additionally, the consultant will be responsible for project administration, development of modeling, estimating, monitoring and tracking aspects of green infrastructure techniques.

**Challenges:** Program efforts include green infrastructure/stormwater management efforts that result in the reduction of CSO discharge from 17 outfalls in Upper Rouge Tributary Area.

Туре	Status	Туре	Start Date	CUST			al Year			
1,400	Status	1700	Start Date			2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Closed	S/D/CA/C	Dec 2013	Dec 2022	\$16,000,000					

## **PC-799 Crowell Rec Center and EcoSite Modifications**

Status: Closed

Significance: Reduce volume to URT (outfalls 059-69, 072-075, 077, 079)

Location: Riverdale neighborhood (Crowell) and Warrendale neighborhood

(EcoSites)

**Driver:** DWSD NPDES Permit No. MI0022802

**Scope of Work:** Construct permeable block pavement in the center parking spaces and two bioretention islands to collect runoff within and tributary to the north parking lot and the south parking lot. For EcoSites, modify 2 of 4 initial designs to divert runoff from opposite side of the street into bioretention cells to double the tributary area at a reasonable cost.

**Challenges:** Coordination of paving and plantings with recreation center usage.



		D-Design	Start	Finish	Total	Projected	d Expenditu	res by Fisc	al Year	
Туре	Status	C- Construction	Date	Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Closed	С	Nov 2017	Dec 2022	\$847,000	\$3,000				

## PC-801A Oakman Blvd

Status: Active -Construction Complete; Project in the Planting

Maintenance Phase

Significance: Reduce volume to URT (outfalls 059-69, 072-075, 077,

079)

Location: Aviation neighborhood

**Driver:** DWSD NPDES Permit No. MI0022802; basement back-ups

**Scope of Work:** Constructed a series of bioretention and underground storage practices within the median to manage runoff from 62.5 acres. The proposed work includes routing stormwater runoff from the tributary areas to either the surface practices within the median or to the sub-surface storage practices based on elevation of the influent.

**Challenges:** Coordination with combining GSI and water main into one project.

					Total	Projected Exp	enditures by	Fiscal Year	r	
Туре	Status	Project Type	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Active	С	8/1/2019	8/1/2024	\$8,694,168	\$20,000	\$20,000	\$20,000		



## PC-800 O'Shea Park

**Status:** Active/Maintenance Period

Significance: Reduce volume to URT (outfalls 059-69, 072-075, 077, 079)

**Location:** Greenfield Road and I-96

**Driver:** DWSD NPDES Permit No. MI0022802

**Scope of Work:** Construction of approximately 14,000 square feet of a bioretention basin; will capture runoff from within the park and the majority of the flow along Capitol Street and Rutherford Street.

**Challenges:** Coordination with GSD for simultaneously occurring park renovation project.



_		D-Design			Total	Projected	Expenditur	es by Fisca	l Year	
Туре	Status	C- Construction	Start Date	Finish Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Active	С	April 2018	Dec 2021	\$587,000	\$10,000				

## PC-806 Charles H Wright Academy

Status: New

 $\textbf{Significance:} \ \textbf{Installation of large GSI that collect and manage}$ 

stormwater.

**Location:** Charles Wright and Ludington Schools

**Driver:** DWSD NPDES Permit No. MI0022802

**Scope of Work:** Construct large scale GSI practices that collect and manage stormwater from Charles Wright. Overflow from the GSI practices is conveyed to the Upper Rouge River through sheet flow.

**Challenges:** Coordination with Detroit Public Schools for agreements and construction.



		D-Design				Pro	jected Exp	enditures k	y Fiscal Ye	ar
Туре	Status	C- Construction	Start Date	Finish Date	Total Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	New	C/D	4/1/2021	4/1/2024	\$1,530,000	\$686,736	\$45,000	\$37,900		

## **Chandler Park Drive (CIPMP)**

Status: New


**Significance:** The stormwater management practice along Chandler Park drive will contribute to runoff reduction.

**Location:** Chandler Park Drive

**Driver:** Optimize the capacity in the sewer system through GSI implementation.

**Scope of Work**: Construct bioretention cells mirroring the natural landscape with a shallow grass swale in the planting strip between the sidewalk and road.

Challenges: N/A





# Capital Partnership Program St. Paul Tabernacle


**Status:** Procurement

**Driver:** DWSD NPDES Permit No. MI0022802 - To help customer reduce the drainage charges and aid in reduction of stormwater flows to the sewer system.

Significance: Stormwater runoff reduction

Location: St. Paul Tabernacle

**Scope of Work:** The work consists of installation of green stormwater infrastructure (GSI), which includes approximately 5,000 cubic feet of underground arch detention system, two rain gardens and all associated storm sewer piping and structures. St. Paul Tabernacle will utilize the CPP funds to implement the stormwater management on the property.



**Purpose:** To comply with regulatory requirements and promote environmental sustainability, DWSD has initiated the Capital Partnership Program (CPP) that will leverage public resources to help customers finance implementation of stormwater management measures at their sites. The CPP provides for DWSD's payments through reimbursements of customer (non-residential) expenses of up to 50% of the cost of approved Green Stormwater Infrastructure (GSI) measures up to a maximum payment of \$50,000, subject to DWSD's CPP policy and administrative procedures. CPP provides up to \$5.0 million per year to fund installation of approved GSI projects

Challenges: N/A

Туре	Status	D-Design	Start Date	Finish Date	Total Estimated	Р	rojected Ex	penditures l	y Fiscal Yea	ar
1,40		C-Construction			Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	New	D			\$175,000	\$5,000				

## **CS-1884A Green Infrastructure Program Management**

**Status:** Active


Significance: To comply with the DWSD NPDES Permit No. MI0022802 and reduce

CSO events.

Location: Upper Rouge Tributary Area

**Driver:** DWSD NPDES Permit No. MI0022802

**Scope of Work:** To study, design and develop bid documentation and provide construction oversight of green infrastructure implementation. Additionally, the consultant will be responsible for project administration, development of modeling, estimating, monitoring and tracking aspects of green infrastructure techniques.




**Challenges:** To locate and install green infrastructure/stormwater management practices that result in the reduction of CSO discharge from 17 outfalls in Upper Rouge Tributary Area.

_		D-Design	Start	Finish	Total		Projected E	xpenditures by	y Fiscal Year	
Туре	Status	C- Construction	Date	Date	Estimated Cost	2021-22	2022-23	2023-24	2024-25	2025-26
Sewer	Active	S/D/CA	8/1/2019	8/1/2026	\$12,000,000	\$2,500,000	\$2,500,000	\$2,500,000	\$1,000,000	\$1,000,000

# APPENDIX B – MAPS OF CIP PROJECT BY COUNCIL DISTRICT




District 1 Active Projects, Condition Assessment/Evaluation, Planning, and Design




O'Hair Park Westwood Park


District 1 Active Projects, Condition Assessment/Evaluation, Planning, and Design



District 2 Active Projects, Condition Assessment/Evaluation, Planning, and Design




## **DPW Street Program**




---- DPW Streetscapes

District 2 Active Projects, Condition Assessment/Evaluation, Planning, and Design



## **DPW Street Program**




---- 2020 DPW Streetscapes

District 3 Active Projects, Condition Assessment/Evaluation, Planning, and Design




## **DPW Street Program**





---- DPW Streetscapes


District 4 Active Projects, Condition Assessment/Evaluation, Planning, and Design




District 4 Active Projects, Condition Assessment/Evaluation, Planning, and Design









District 6 Active Projects, Condition Assessment/Evaluation, Planning, and Design




District 6 Active Projects, Condition Assessment/Evaluation, Planning, and Design



District 7 Active Projects, Condition Assessment/Evaluation, Planning, and Design



District 7 Active Projects, Condition Assessment/Evaluation, Planning, and Design





# APPENDIX C - STREET TABLE OF CIP PROJECTS



Type	Phase	Activity	Project ID	Location	Districts	Length	Street	Street From	Street To
Water	Procurement	Repair	CS-1909 DWSD	24th St. Jefferson W. to C & O Rail Road	6		24th St.	Jefferson W.	C & O Rail Road
Sewer	Procurement	•	DWS-916	2nd Ave Bethune to Grand Blvd	5	499	2nd Ave	Bethune	Grand Blvd
Water	Procurement	•	WS-718	3rd St Euclid St to Virginia Park St	5	440	3rd St	Euclid St	Virginia Park St
Water	Procurement	Replace	WS-718	3rd St Virginia Park St to Pallister St	5	1,392	3rd St	Virginia Park St	Pallister St
Water	Design	Replace	WS-716	Alfred St Antoine to Beaubien	5	1,118	Alfred	St Antoine	Beaubien
Sewer	Procurement	Repair	DWS-916	Alfred Brush to Brush	5	24	Alfred	Brush	Brush
Sewer	Procurement	Repair	DWS-916	Alfred Chyrsler to Chrysler	5	15	Alfred	Chyrsler	Chyrsler
Water	Design	Replace	WS-713	Alfred Brush Ford Park Lenox to Newport park boundary	4	455	Alfred Brush Ford Park	Lenox	Newport
Water	Design	Replace	WS-713	Algonquin Essex to Avondale	4	708	Algonquin	Essex	Avondale
Water	Construction	Replace	WS-712	Alstead St Moross Rd northeast to Kingsville St	4		Alstead S	Moross Rd northeast	Kingsville St
Water	Design	Replace	WS-713	Alter Essex to Klenk	4	3,261	Alter	Essex	Klenk
Water	Construction	_	WS-712	Anatole St Canyon St to Mack Ave	4	1,133	Anatole	Canyon St	Mack Ave
Sewer	Construction	Repair	DWS-907	Annchester Rd Santa Maria St to McNichols Rd	1		Annchester Rd	Santa Maria St	McNichols Rd
Water	Procurement	Repair	CS-1909 DWSD	Appoline Joy to Tireman	7		Appoline	•	Tireman
Water	Procurement		CS-1909 DWSD	Artesian Van Buren to Constance	7		Artesian		Constance
Water	Procurement	-	CS-1909 DWSD	Artesian Kirkwood to Paul	7		Artesian		Paul
Water	Design	Replace	WS-713	Ashland Jefferson to south of Fox River	4				Fox River
Water	Procurement	_	CS-1909 DWSD	Ashton W. Davison to Dead End	1		Ashton	W. Davison	Dead End
Water	Procurement	•	CS-1909 DWSD	Ashton Curtis to Seven Mile	1		Ashton	Curtis	Seven Mile
Sewer	Construction	-	DWS-907	Ashton Ave Florence St to Verne Ave	1		Ashton Ave	Florence St	Verne Ave
Sewer	Construction	-	DWS-907	Ashton Ave Florence St to Puritan Ave	1		Ashton Ave		Puritan Ave
Sewer	Construction	•	DWS-907	Ashton Rd Puritan Ave to Pilgrim St			Ashton Rd		Pilgrim St
Sewer	Construction	•	DWS-907	Ashton Rd Midland St to Keeler St			Ashton Rd	Midland St	Keeler St
Sewer	Procurement	-	DWS-916	Atkinson Woodford to 2nd Ave	5		Atkinson	Woodford	2nd Ave
Water	Procurement	_	CS-1909 DWSD	Auburn Fenkell to Midland			Auburn		Midland
Water	Procurement	-	WS-715	Auburn St Grand River Avenue to Outer Drive			Auburn St		Outer Drive
Water	Procurement	•	CS-1909 DWSD	Avon Outer Drive to Seven Mile	1	3,921			Seven Mile
Sewer	Construction	-	DWS-907 WS-712	Avon Rd Gainsborough Rd to Grand River Ave	1		Avon Rd Badluck Memorial Park (north)	Gainsborough Rd	Grand River Ave
Water	Construction Procurement	_	WS-712 DWS-916	Canyon St northeast of Badluck Memorial Park (north) Beaubien Mack to Eliot	5		Beaubien	•	Balduck Park Paring Lot Eliot
Sewer Water	Construction	•	WS-706	Beaverland Ave. Sawyer Ave. to Tireman	1		Beaverland Ave.	Sawyer Ave.	Tireman
Water	Construction	-	WS-700 WS-712	Berden St Canyon St northeast to Moross Rd	1		Berden St	Canyon St northeast	Moross Rd
Sewer	Procurement		DWS-916	Bethune 3rd Ave to John C Lodge FWY	5		Bethune	•	John C Lodge FWY
Water	Procurement		WS-718	Bethune St 3rd St to John C Lodge Fwy	5		Bethune St	3rd St	John C Lodge Fwy
Water	Procurement	-	WS-715	Blackstone St Grand River Avenue to Florence	1		Blackstone St	Grand River Avenue	Florence
Sewer	Procurement	_	DWS-916	Blaine Wooward to 3rd Ave	5		Blaine		3rd Ave
Sewer	Construction	•	DWS-908	Bluehill Harper to Berden	4		Bluehill	Harper	Berden
Sewer	Construction	-	DWS-908	Bluehill Linville to Southampton	4		Bluehill	•	Southampton
Sewer	Construction	-	DWS-908	Bluehill Minneapolis to Mack	4		Bluehill		Mack
Water	Construction	•	WS-712	Bluehill St Chandler Park Dr southeast to Southampton St	4	,	Bluehill S	Chandler Park Dr southeast	
Water	Construction	-	WS-707	Brace Warren to Paul	7		Brace		Paul
Water	Procurement	_	WS-715	Braile St Florence to Puritan	1	628	Braile St	Florence	Puritan
Water	Procurement	_	WS-715	Bramell St McNichols Rd to Puritan	1	2,530	Bramell St	McNichols Rd	Puritan
Water	Procurement	Repair	CS-1909 DWSD	Brammel Tireman to Constance	7	1,693	Brammel	Tireman	Constance
Sewer	Construction	Repair	DWS-907	Bretton Dr Outer Dr to Huntington Rd	1	30	Bretton Dr	Outer Dr	Huntington Rd
Sewer	Construction	Repair	DWS-907	Bretton Dr Huntington Rd to Huntington Rd	1	40	Bretton Dr	Huntington Rd	Huntington Rd
Sewer	Construction	Repair	DWS-907	Bretton Dr Outer Dr to Shaftsbury Ave	1	10	Bretton Dr	Outer Dr	Shaftsbury Ave
Sewer	Construction	Repair	DWS-907	Bretton Dr Outer Dr to Shaftsbury Ave	1	10	Bretton Dr	Outer Dr	Shaftsbury Ave
Sewer	Construction	Repair	DWS-907	Bretton Dr Warwick St to Avon Rd	1	10	Bretton Dr	Warwick St	Avon Rd
Sewer	Construction	Repair	DWS-907	Bretton Dr Warwick St to Avon Rd	1	10	Bretton Dr	Warwick St	Avon Rd
Sewer	Construction	Repair	DWS-907	Bretton Dr Shaftsbury Ave to Warwick St	1		Bretton Dr	Shaftsbury Ave	Warwick St
Sewer	Construction	Repair	DWS-907	Bretton Dr Keeler St to Keeler St	1		Bretton Dr	Keeler St	Keeler St
Sewer	Construction	_	DWS-907	Bretton Dr Glastonbury Ave to Avon Rd	1		Bretton Dr	•	Avon Rd
Water	Procurement	_	WS-715	Burgess Verne to Puritan	1		Burgess		Puritan
Water	Procurement	•	WS-715	Burgess McNichols Rd to Verne	1		Burgess	McNichols Rd	Verne
Water	Procurement	Replace	WS-715	Burt Rd McNichols Rd to Grand River Ave	1	780	Burt Rd	McNichols Rd	Grand River Ave

Type	Phase	Activity	Project ID	Location	Districts	Length	Street	Street From	Street To
Water	Procurement	Repair	CS-1909 DWSD	Burt Road Seven Mile to Vassar	1	1,339	Burt Road	Seven Mile	Vassar
Water	Procurement	Replace	WS-715	Burt St Grand River Avenue to Florence	1	1,011	Burt St	Grand River Avenue	Florence
Water	Construction	-	WS-712	Cadieux Rd Warren Ave to New York St	4	286	Cadieux Rd	Warren Ave	New York St
Water	Procurement	Repair	CS-1909 DWSD	Cadieux Road Harper Avenue to Munich Avenue	4	,	Cadieux Road	Harper Avenue	Munich Avenue
Sewer	Construction	Replace	DWS-908	Canyon Chester to Moon	4	174	Canyon	Chester	Moon
Sewer	Construction	Repair	DWS-908	Canyon Chester to Moon	4	140	Canyon	Chester	Moon
Water	Construction	Replace	WS-712	Canyon St Mallina St southeast to Berden St	4	352	Canyon St	Mallina St southeast	Berden St
Water	Construction	Replace	WS-712	Canyon St Warren Ave south to Mack Ave	4	943	Canyon St	Warren Ave south	Mack Ave
Water	Construction	Replace	WS-712	Canyon St Edsel Ford Service Dr southeast to Rockcastle Dr	4	424	Canyon St	Edsel Ford Service Dr south	Rockcastle Dr
Water	Procurement	Repair	CS-1909 DWSD	Cathedral Grandville to Southfield Freeway	7	1,352	Cathedral	Grandville	Southfield Freeway
Water	Construction	Repair	WS-712	the intersection of Cadieux Rd and Chandler Park Dr	4	74	Chadieux Rd	Chandler Park Dr (North)	Chandler Park Dr (South)
Water	Procurement	Replace	WS-715	Chalfonte St Artesian to Stahelin	1	307	Chalfonte St	Artesian	Stahelin
Water	Design	Replace	WS-713	Chalmers Essex to Scripps	4	2,607	Chalmers	Essex	Scripps
Water	Design	Replace	WS-713	Chalmers Freud to Jefferson	4	1,155	Chalmers	Freud	Jefferson
Water	Procurement	Repair	CS-1909 DWSD	Chalmers Ave. Warren Avenue to Mack Avenue	4	3,649	Chalmers Ave.	Warren Avenue	Mack Avenue
Water	Procurement	Repair	CS-1909 DWSD	Chalmers Ave. Mack Avenue to Jefferson Avenue	4	5,459	Chalmers Ave.	Mack Avenue	Jefferson Avenue
Water	Procurement	Repair	CS-1909 DWSD	Chalmers Ave. Mack Avenue to Jefferson Avenue	4	5,508	Chalmers Ave.	Mack Avenue	Jefferson Avenue
Sewer	Procurement	Repair	DWS-916	Chandler Woodward to 2nd Ave	5	235	Chandler	Woodward	2nd Ave
Water	Construction	Replace	WS-712	Chandler Park Dr Lannoo St northeast to Moross Rd	4	566	Chandler Par	Lannoo St northeast	Moross Rd
Water	Construction	Replace	WS-712	Chandler Park Dr Lodewyck St northeast to Radnor St	4	556	Chandler Par	Lodewyck St northeast	Radnor St
Water	Construction	Replace	WS-712	Chandler Park Dr Cadieux Rd northeast to Bluehill St	4	695	Chandler Park Dr	Cadieux Rd northeast	Bluehill St
Water	Procurement	Repair	CS-1909 DWSD	Chatham Orangelawn to Plymouth	7	1,744	Chatham	Orangelawn	Plymouth
Sewer	Construction	Repair	DWS-908	Chester Marseillees to University	4	337	Chester	Marseillees	University
Water	Construction	-	WS-712	Chester St and Marseilles St intersection	4	508	Chester St	Maseilles	Farmbrook
Water	Construction	Replace	WS-712	Chester St at Neff Ave intersection	4	73	Chester St	Neff Ave	125 FT West
Sewer	Procurement	-	DWS-916	Chrysler Eliot to Wilkins	5	3	Chrysler	Eliot	Wilkins
Sewer	Procurement	Repair	DWS-916	Chrysler Mack to Watson	5	177	Chrysler	Mack	Watson
Water	Design	Replace	WS-716	Chrysler Dr Watson to Winder	5	2,416	Chrysler Dr	Watson	Winder
Water	Construction	Replace	WS-712	Cincinnati St Cadieux Rd northeast to end of street	4	655	Cincinnati	Cadieux Rd northeast	end of street
Sewer	Construction	Repair	DWS-908	Cincinnati Guilford to Cadieux	4	10	Cincinnati	Guilford	Cadieux
Sewer	Construction	Replace	DWS-908	Cincinnati Guilford to Cadieux	4	655	Cincinnati	Guilford	Cadieux
Water	Procurement	Repair	CS-1909 DWSD	Clairview (Btwn Windsor & Waveny) Neff to Westward to Dead End	4	186	Clairview (Btwn Windsor & W	Neff	Westward to Dead End
Water	Construction	Repair	WS-707	Codding Grand River to Margareta	1	1,047	Codding	Grand River	Margareta
Water	Design	Replace	WS-713	Conner Essex to Gate Valve at Park	4		Conner		Park
Water	Design	Replace	WS-713	Continental Freud to Jefferson	4		Continental	Freud	Jefferson
Water		Repair	CS-1909 DWSD	Cooley Pembroke to St. Martins	1		Cooley	Pembroke	St. Martins
Sewer	Construction	-	DWS-908	Cornwall Guilford to Cadieux	4		Cornwall	Guilford	Cadieux
Sewer	Construction	•	DWS-908	Cornwall Cadieux to Guilford	4		Cornwall	Cadieux	Guilford
Water	Construction	•	WS-707	Coyle Fenkell to Grand River	1		Coyle	Fenkell	Grand River
Water	Procurement	_	CS-1909 -CIPMO	Davison	6		Davison	St Antoine St	Chrysler Service Dr.
Water	Procurement	_	CS-1909 DWSD	Davison Avenue Cheyenne to Wyoming	7		Davison Avenue	Cheyenne	Wyoming
Water	Procurement	_	CS-1909 DWSD	Davison Avenue Wyoming to Livernois	7		Davison Avenue	•	Livernois
Water	Procurement	-	CS-1909 DWSD	Davison Avenue McNichols to Syracuse	7	,	Davison Avenue	McNichols	Syracuse
Water	Procurement	_	WS-718	Delaware Woodward Ave to 3rd St	5		Delaware	Woodward Ave	3rd St
Water	Procurement	_	CS-1909 DWSD	Delaware St. 2nd Street to Woodward	5		Delaware St.	2nd Street	Woodward
Water	Construction	_	WS-712	Detroit St Cadieux Rd northeast to Guilford St	4		Detroit	Cadieux Rd northeast	Guilford St
Sewer	Construction	_	DWS-908	Detroit Cadieux to Guilford	4		Detroit	Cadieux	Guilford
Sewer	Construction	•	DWS-908	Detroit Cadieux to Guilford	4		Detroit	Cadieux	Guilford
Water	Design	Replace	WS-716	Division Beaubien to Winder	5	,	Division	Beaubien	Winder
Water		Replace	WS-715	Dolphin St Grove to Dehner	1		Dolphin St	Grove	Dehner
Water	Design	Lining	WS-713	Drexel Averhill (added new valve) to Avondale South side	4		Drexel	Averhill	Avondale
Water	Design	Replace	WS-713	Drexel/Riverside Dr Averhill to dead-end south of Scripps	4	· · · · · · · · · · · · · · · · · · ·	Drexel/Riverside Dr	Averhill	Scripps
Water	Construction	_	WS-707	E. Outer Drive Wallingford to 250 ft South of Cornwall	4		E. Outer Drive	Wallingford	Cornwall St
Water	Construction	•	WS-706	E. Outer Drive Dequindre to Mitchell	4		E. Outer Drive	Dequindre	Mitchell
Sewer	Procurement	-	DWS-916	Easement Benton Chrysler to East	5		Easement Benton	•	East
Sewer	Procurement	Kepair	DWS-916	Easement E. 2nd Ave Chandler to Bethune	5	244	Easement E. 2nd Ave	Chandler	Bethune

Type	Phase	Activity	Project ID	Location	Districts	Length	Street	Street From	Street To
Sewer	Construction	Repair	DWS-907	Easement E. of Bretton Dr Keeler St to Grand River Ave	1	10	Easement E. of Bretton Dr	Keeler St	Grand River Ave
Sewer	Construction	Repair	DWS-908	Easement E. of Cadieux Sioux to Detroit	4	294	Easement E. of Cadieux	Sioux	Detroit
Sewer	Construction	Repair	DWS-907	Easement E. of Edinborough Rd McNichols Rd to Grove St	1	490	Easement E. of Edinborough R	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Easement E. of Edinborough Rd Verne Ave to Florence St	1	598	Easement E. of Edinborough R	Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Easement E. of Evergreen Ave Grove St to Verne Ave	1	678	Easement E. of Evergreen Ave	Grove St	Verne Ave
Sewer	Construction	Repair	DWS-907	Easement E. of Evergreen Rd Verne Ave to Florence St	1	44	Easement E. of Evergreen Rd	Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Easement E. of Evergreen Rd Verne Ave to Florence St	1	10	Easement E. of Evergreen Rd	Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Easement E. of Evergreen Rd McNichols Rd to Grove St	1	10	Easement E. of Evergreen Rd	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Easement E. of Evergreen Rd McNichols Rd to Grove St	1	10	Easement E. of Evergreen Rd	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Easement E. of Evergreen Rd McNichols Rd to Grove St	1	10	Easement E. of Evergreen Rd	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Easement E. of Glastonbury Ave Lancashire St to Grand Rive Alley	1	10	Easement E. of Glastonbury Av	Lancashire St	Grand Rive Alley
Sewer	Construction	Repair	DWS-907	Easement E. of Glastonbury Rd Verne Ave to Florence St	1	10	Easement E. of Glastonbury Rd	l Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Easement E. of Glastonbury Rd Grove St to Verne Ave	1	10	Easement E. of Glastonbury Rd	l Grove St	Verne Ave
Sewer	Construction	Repair	DWS-907	Easement E. of Glastonbury Rd Grove St to Verne Ave	1	10	Easement E. of Glastonbury Rd	l Grove St	Verne Ave
Sewer	Construction	Repair	DWS-907	Easement E. of Glastonbury Rd McNichols Rd to Grove St	1	10	Easement E. of Glastonbury Rd	l McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Easement E. of Glastonbury Rd Puritan St to Pilgrim St	1	39	Easement E. of Glastonbury Rd	l Puritan St	Pilgrim St
Sewer	Construction	Repair	DWS-907	Easement E. of Huntington McNichols Rd to Grove St	1	491	Easement E. of Huntington	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Easement E. of Huntington Rd Grove St to Verne Ave	1	697	Easement E. of Huntington Rd	Grove St	Verne Ave
Sewer	Construction	Repair	DWS-907	Easement E. of Outer Dr Verne Ave to Florence St	1	90	Easement E. of Outer Dr	Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Easement E. of Plainview Ave McNichols Rd to Grove St	1	491	Easement E. of Plainview Ave	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Easement E. of Plainview Ave Grove St to Verne Ave	1	679	Easement E. of Plainview Ave	Grove St	Verne Ave
Sewer	Construction	Repair	DWS-907	Easement E. of Plainview Ave Verne Ave to Florence St	1	457	Easement E. of Plainview Ave	Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Easement E. of Rosemont Ave Florence St to Puritan Ave	1	619	Easement E. of Rosemont Ave	Florence St	Puritan Ave
Sewer	Construction	Repair	DWS-907	Easement E. of Rosemont Ave Pilgrim St to Midland St	1	1,312	Easement E. of Rosemont Ave	Pilgrim St	Midland St
Sewer	Construction	Replace	DWS-907	Easement E. of Shaftsbury Ave Verne Ave to Florence St	1	624	Easement E. of Shaftsbury Ave	Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Easement E. of Shaftsbury Ave Verne Ave to Florence St		29	Easement E. of Shaftsbury Ave	Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Easement E. of Stahelin Ave Grove St to Verne Ave	1	316	Easement E. of Stahelin Ave	Grove St	Verne Ave
Sewer	Construction	Repair	DWS-907	Easement E. of Warwick St McNichols Rd to Grove St	1	10	Easement E. of Warwick St	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Easement E. of Westmoreland Rd Verne Ave to Florence St	1	346	Easement E. of Westmoreland	I Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Easement E. of Westmoreland Rd Verne Ave to Florence St	1		Easement E. of Westmoreland		Florence St
Sewer	Construction	Repair	DWS-907	Easement E. of Westmoreland Rd McNichols Rd to Grove St	1		Easement E. of Westmoreland		Grove St
Sewer	Construction	Repair	DWS-907	Easement E. of Westmoreland Rd McNichols Rd to Grove St	1	471	Easement E. of Westmoreland	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Easement E. of Westmoreland Rd Grove St to Verne Ave	1	697	Easement E. of Westmoreland		Verne Ave
Sewer	Procurement	•	DWS-916	Easement E. St Antoine Wilkins to Alfred	5		Easement E. St Antoine	Wilkins	Alfred
Sewer	Procurement	•	DWS-916	Easement Erskin East to Beaubien	5		Easement Erskin	East	Beaubien
Sewer	Procurement	•	DWS-916	Easement Fisher FWY E Fisher Service Drive to Montcalm	5		Easement Fisher FWY	E Fisher Service Drive	Montcalm
Sewer	Procurement	•	DWS-916	Easement N. Eliot Beaubien to East	5		Easement N. Eliot	Beaubien	East
Sewer	Construction	-	DWS-908	Easement N. of Cadieux munich to Cincinnati	4		Easement N. of Cadieux	munich	Cincinnati
Sewer	Construction	-	DWS-908	Easement N. of Cadieux Waveney to Detroit	4		Easement N. of Cadieux	Waveney	Detroit
Sewer	Construction	•	DWS-908	Easement N. of Mack Woodhall to Guilford	4		Easement N. of Mack	Woodhall	Guilford
Sewer	Construction	_	DWS-908	Easement N. of Moross Edgefield to Tyrone	4		Easement N. of Moross	Edgefield	Tyrone
Sewer	Construction	_	DWS-908	Easement N. of Moross Edgefield to Tyrone	4		Easement N. of Moross	Edgefield	Tyrone
Sewer	Construction	•	DWS-908	Easement N. of Warren Cadieux to Bluehill	4		Easement N. of Warren	Cadieux	Bluehill
Sewer	Procurement	-	DWS-916	Easement S. Bethune Woodward to 2nd Ave	5		Easement S. Bethune	Woodward	2nd Ave
Sewer	Procurement	-	DWS-916	Easement S. Chandler Woodward to Delaware	5	,	Easement S. Chandler	Woodward	Delaware
Sewer	Procurement	_	DWS-916	Easement S. Eliot St Antoine to Beaubien	5		Easement S. Eliot	St Antoine	Beaubien
Sewer	Procurement	_	DWS-916	Easement S. Euclid Woodward to John C Lodge FWY	5		Easement S. Euclid	Woodward	John C Lodge FWY
Sewer	Procurement	-	DWS-916	Easement S. Gladstone Woodward to John C Lodge FWY	5		Easement S. Gladstone	Woodward	John C Lodge FWY
Sewer	Procurement	•	DWS-916	Easement S. Hazlewood Woodward to John C Lodge FWY	5	,	Easement S. Hazlewood	Woodward	John C Lodge FWY
Sewer	Procurement	-	DWS-916	Easement S. Lothrop Wooward to John C Lodge FWY	5		Easement S. Lothrop	Wooward	John C Lodge FWY
Sewer	Construction	_	DWS-908	Easement S. of Berden Lodewyck to Marseilles	4		Easement S. of Berden	Lodewyck	Marseilles
Sewer	Procurement	_	DWS-916	Easement S. of Blaine Woodward to John C Lodge FWY	5		Easement S. of Blaine	Woodward	John C Lodge FWY
Sewer	Construction	_	DWS-908	Easement S. of Cincinnati Guilford to Cadieux	4		Easement S. of Cincinnati	Guilford	Cadieux
Sewer	Procurement	-	DWS-916	Easement S. of Clairmount at 2nd Ave	5		Easement S. of Clairmount	2nd Ave	2nd Ave
Sewer	Construction	-	DWS-907	Easement S. of Florence St Evergreen Rd to Westmoreland Rd	1		Easement S. of Florence St	Evergreen Rd	Westmoreland Rd
Sewer	Construction	Kepair	DWS-907	Easement S. of Florence St Shaftsbury Ave to Warwick St	1	10	Easement S. of Florence St	Shaftsbury Ave	Warwick St

Type	Phase	Activity	Project ID	Location	Districts	Length	Street	Street From	Street To
Sewer	Construction	Repair	DWS-907	Easement S. of Florence St Shaftsbury Ave to Warwick St	1		Easement S. of Florence St	Shaftsbury Ave	Warwick St
Sewer	Construction	Repair	DWS-907	Easement S. of McNichols Rd Westmoreland Rd to Edinborough Rd	1	10	Easement S. of McNichols Rd	Westmoreland Rd	Edinborough Rd
Sewer	Construction	Repair	DWS-907	Easement S. of McNichols Rd Evergreen Rd to Plainview Ave	1		Easement S. of McNichols Rd	· ·	Plainview Ave
Sewer	Construction	Repair	DWS-907	Easement S. of McNichols Rd Huntington Rd to Outer Dr	1	227	Easement S. of McNichols Rd	Huntington Rd	Outer Dr
Sewer	Construction	Repair	DWS-907	Easement S. of McNichols Rd Plainview Ave to Westmoreland Rd	1	208	Easement S. of McNichols Rd	Plainview Ave	Westmoreland Rd
Sewer	Construction	Repair	DWS-907	Easement S. of McNichols Rd Edinborough Rd to Huntington Rd	1		Easement S. of McNichols Rd	· ·	Huntington Rd
Sewer	Construction	Repair	DWS-907	Easement S. of McNichols Rd Warwick St to Sunderland Rd	1		Easement S. of McNichols Rd	Warwick St	Sunderland Rd
Sewer	Procurement	Repair	DWS-916	Easement S. of Pingress Wooward to John C Lodge FWY	5	2,225	Easement S. of Pingress	Wooward	John C Lodge FWY
Sewer	Construction	-	DWS-908	Easement S. of Waveney Guilford to Cadieux	4	549	Easement S. of Waveney	Guilford	Cadieux
Sewer	Procurement	_	DWS-916	Easement S. Philadelphia Wooward to John C. Lodge FWY	5		Easement S. Philadelphia	Wooward	John C. Lodge FWY
Sewer	Procurement	_	DWS-916	Easement S. Seward Woodward to 3rd St	5		Easement S. Seward	Woodward	3rd St
Sewer	Procurement	-	DWS-916	Easement S. Taylor Woodward to John C Lodge FWY	5		Easement S. Taylor	Woodward	John C Lodge FWY
Sewer	Procurement	-	DWS-916	Easement S. Virginia Woodward to John C. Lodge FWY	5		Easement S. Virginia	Woodward	John C. Lodge FWY
Sewer	Procurement	-	DWS-916	Easement S. Wilkins Chrysler to St Antoine	5		Easement S. Wilkins	Chrysler	St Antoine
Sewer	Procurement	-	DWS-916	Easement W. 2nd Ave Atkinson to Clairmount	5		Easement W. 2nd Ave	Atkinson	Clairmount
Sewer	Procurement	-	DWS-916	Easement W. 2nd Ave Lothorp to Grand Blvd	5	207	Easement W. 2nd Ave	Lothorp	Grand Blvd
Sewer	Procurement	_	DWS-916	Easement W. 2nd Ave between Atkinson and Clairmount	5	9	Easement W. 2nd Ave	Atkinson	Clairmount
Sewer	Procurement	-	DWS-916	Easement W. 3rd Ave Seward to Lathrop	5		Easement W. 3rd Ave	Seward	Lathrop
Sewer	Procurement	-	DWS-916	Easement W. 3rd Ave Euclid to Virginia Park	5		Easement W. 3rd Ave	Euclid	Virginia Park
Sewer	Procurement	-	DWS-916	Easement W. Chrysler Benton to Winder	5		Easement W. Chrysler	Benton	Winder
Sewer	Procurement	-	DWS-916	Easement W. East St Eliot to Watson	5	661	Easement W. East St	Eliot	Watson
Sewer	Construction	-	DWS-908	Easement W. of Bluehill Harper to Berden	4	369	Easement W. of Bluehill	Harper	Berden
Sewer	Construction	-	DWS-908	Easement W. of Farmbrook Minvera to Berden	4	97	Easement W. of Farmbrook	Minvera	Berden
Sewer	Construction	-	DWS-908	Easement W. of Farmbrook Southampton to Frankfort	4	305	Easement W. of Farmbrook	Southampton	Frankfort
Sewer	Construction	-	DWS-908	Easement W. of Farmbrook Cornwall to Munich	4		Easement W. of Farmbrook	Cornwall	Munich
Sewer	Construction	-	DWS-908	Easement W. of Farmbrook Chester to Linville	4		Easement W. of Farmbrook	Chester	Linville
Sewer	Construction	-	DWS-908	Easement W. of Farmbrook Warren to Munich	4			Warren	Munich
Sewer	Construction	-	DWS-908	Easement W. of Hereford Chester to Minvera	4	387	Easement W. of Hereford	Chester	Minvera
Sewer	Construction	-	DWS-908	Easement W. of Hereford Berden to Southampton	4		Easement W. of Hereford	Berden	Southampton
Sewer	Construction		DWS-908	Easement W. of Hereford Southampton to Warren	4		Easement W. of Hereford	Southampton	Warren
Sewer	Construction		DWS-908	Easement W. of Hereford Munich to Mack	4		Easement W. of Hereford	Munich	Mack
Sewer	Construction	-	DWS-908	Easement W. of Lodewyck Southampton to Frankfort	4	629	Easement W. of Lodewyck	Southampton	Frankfort
Sewer	Construction	•	DWS-908	Easement W. of Lodewyck Warren to Cornwall	4		Easement W. of Lodewyck	Warren	Cornwall
Sewer	Construction	-	DWS-908 DWS-908	Easement W. of Lodewyck Chandler Park to Frankfort Easement W. of Marseille Edsel Ford Hwy to Chester	4		Easement W. of Lodewyck Easement W. of Marseille	Chandler Park	Frankfort Chester
Sewer	Construction	_	DWS-908	Easement W. of Marseille Chester to Minyera	4		Easement W. of Marseille	Edsel Ford Hwy	Minvera
Sewer	Construction Construction	-	DWS-908	Easement W. of Marseille Berden to Frankfort	4		Easement W. of Marseille	Chester Berden	Frankfort
Sewer Sewer	Construction	-	DWS-908	Easement W. of Marseille Southampton to Munich	4		Easement W. of Marseille	Southampton	Munich
Sewer	Construction	-	DWS-908	Easement W. of Marseille Munich to Mack	4		Easement W. of Marseille	Munich	Mack
Sewer	Construction	-	DWS-908	Easement W. of Marseilles Berden to Chandler Park	4		Easement W. of Marseilles	Berden	Chandler Park
Sewer	Construction	-	DWS-908	Easement W. of Marseilles Frankfort to Warren	<del>4</del> Д		Easement W. of Marseilles	Frankfort	Warren
Sewer	Construction	_	DWS-908	Easement W. of Oldtown Harper to Bern	4		Easement W. of Oldtown	Harper	Bern
Sewer	Construction	-	DWS-908	Easement W. of Oldtown Chandler Park to Southampton	4		Easement W. of Oldtown	Chandler Park	Southampton
Sewer	Construction	-	DWS-908	Easement W. of Radnor Chester to Linville	4		Easement W. of Radnor	Chester	Linville
Sewer	Construction	-	DWS-908	Easement W. of Radnor Cornwall to Munich	4		Easement W. of Radnor	Cornwall	Munich
Sewer	Construction	-	DWS-908	Easement W. of University Linville to Chandler Park	4		Easement W. of University	Linville	Chandler Park
Sewer	Construction	-	DWS-908	Easement W. of University Frankfort to Munich	4		Easement W. of University	Frankfort	Munich
Sewer	Construction	_	DWS-908	Easement W. of University Frankfort to Hereford	4		Easement W. of University	Frankfort	Hereford
Sewer	Procurement	-	DWS-916	Easement W. Woodward Taylor to Grand Blvd	5		Easement W. Woodward	Taylor	Grand Blvd
Sewer	Construction		DWS-908	Easement. W. of Bluehill Linville to Southampton	4		Easement. W. of Bluehill	Linville	Southampton
Water	Procurement	_	CS-1909 DWSD	East Grand Blvd Trombly to McDougall	5		East Grand Blvd	Trombly	McDougall
Water	Procurement	_	CS-1909 DWSD	East Grand Blvd Oakland Ave. to Trombly	5		East Grand Blvd	Oakland Ave.	Trombly
Water	Procurement		CS-1909 DWSD	East Grand Blvd Lodge Frwy to Oakland Ave.	5		East Grand Blvd	Lodge Frwy	Oakland Ave.
Water	Procurement	_	CS-1909 DWSD	East Grand Blvd McDougall to Helen	5		East Grand Blvd	McDougall	Helen
Water	Procurement	-	CS-1909 DWSD	East Grand Blvd Helen to Forest	5		East Grand Blvd	Helen	Forest
Water	Procurement	-	CS-1909 DWSD	East Grand Blvd Vernor to E. Jefferson Ave.	5		East Grand Blvd	Vernor	E. Jefferson Ave.
		-				*			

Type	Phase	Activity	Project ID	Location	Districts	Length	Street	Street From	Street To
Water	Design	Replace	WS-713	Eastlawn dead end to Scripps (added new valve)	4		Eastlawn	Scripps	Dead End South
Water	Construction	Replace	DWS-907	Edinborough Rd Bretton Dr north to McNichols Rd	1	3,364	Edinboroug	Bretton Dr North	McNichols Rd
Sewer	Construction	-	DWS-907	Edinborough Rd McNichols Rd to Grove St	1		Edinborough Rd	McNichols Rd	Grove St
Sewer	Construction	•	DWS-907	Edinborough Rd Grove St to Verne Ave	1		Edinborough Rd	Grove St	Verne Ave
Sewer	Construction	•	DWS-907	Edinborough Rd Grove St to Verne Ave	1		Edinborough Rd	Grove St	Verne Ave
Sewer	Construction	Repair	DWS-907	Edinborough Rd Grove St to Grove St	1		Edinborough Rd	Grove St	Grove St
Sewer	Construction	Repair	DWS-908	Edsel Ford Hwy Farmbrook to Hereford	4	552	Edsel Ford Hwy	Farmbrook	Hereford
Sewer	Construction	Repair	DWS-908	Edsel Ford Hwy Moross to Canyon	4	184	Edsel Ford Hwy	Moross	Canyon
Sewer	Procurement	Repair	DWS-916	Euclid Woodward to 2nd Ave	5	260	Euclid	Woodward	2nd Ave
Water	Procurement	Repair	CS-1909 DWSD	Evergreen Elmira to Chicago	7	1,766	Evergreen	Elmira	Chicago
Sewer	Construction	Repair	DWS-907	Evergreen Rd Verne Ave to Verne Ave	1		Evergreen Rd	Verne Ave	Verne Ave
Water	Construction	Replace	WS-712	Farmbrook St Edsel Ford Service Dr to Chandler Park Dr	4		Farmbrook	Edsel Ford Service Dr	Chandler Park Dr
Water	Construction	Replace	WS-712	Farmbrook St Chandler Park Dr southeast to Cornwall St	4		Farmbrook St	Chandler Park Dr southeas	t Cornwall St
Water	Procurement	Repair	CS-1909 DWSD	Faust W. Chicago to Cathedral	7	1,255	Faust	W. Chicago	Cathedral
Water	Procurement	Repair	CS-1909 DWSD	Faust Kirkwood to Dayton	7	765	Faust	Kirkwood	Dayton
Water	Procurement	Repair	CS-1909 DWSD	Faust Dover to Joy	7	619	Faust	Dover	Joy
Water	Procurement	Repair	CS-1909 DWSD	Fielding Tireman to Belton	7	663	Fielding	Tireman	Belton
Sewer	Procurement	Repair	DWS-916	Fisher FWY Beaubien to Brush	5	385	Fisher FWY	Beaubien	Brush
Sewer	Construction	Repair	DWS-907	Florence St Plainview Ave to Westmoreland Rd	1	10	Florence St	Plainview Ave	Westmoreland Rd
Sewer	Construction	Repair	DWS-907	Florence St Evergreen Rd to Plainview Ave	1	10	Florence St	Evergreen Rd	Plainview Ave
Sewer	Construction	Repair	DWS-907	Florence St Edinborough Rd to Huntington Rd	1		Florence St	Edinborough Rd	Huntington Rd
Sewer	Construction	Repair	DWS-907	Florence St Westmoreland Rd to Edinborough Rd	1	10	Florence St	Westmoreland Rd	Edinborough Rd
Sewer	Construction	Repair	DWS-907	Florence St Huntington Rd to Shaftsbury Ave	1	738	Florence St	Huntington Rd	Shaftsbury Ave
Sewer	Construction	Repair	DWS-907	Florence St Warwick St to Outer Dr	1	10	Florence St	Warwick St	Outer Dr
Sewer	Construction	Repair	DWS-907	Florence St Outer Dr to Shaftsbury Ave	1	10	Florence St	Outer Dr	Shaftsbury Ave
Sewer	Construction	Repair	DWS-907	Florence St Outer Dr to Shaftsbury Ave	1	25	Florence St	Outer Dr	Shaftsbury Ave
Water	Procurement	Repair	CS-1909 DWSD	Fourth Street Selden to Calumet	6	1,219	Fourth Street	Selden	Calumet
Water	Construction	Repair	WS-707	Fullerton Petoskey to Dexter	7	1,309	Fullerton	Petoskey	Dexter
Sewer	Construction	Repair	DWS-907	Gainsborough Rd Warwick St to Outer Dr	1	688	Gainsborough Rd	Warwick St	Outer Dr
Sewer	Construction	Replace	DWS-907	Gainsborough Rd Warwick St to Outer Dr	1	451	Gainsborough Rd	Warwick St	Outer Dr
Sewer	Procurement	Repair	DWS-916	Gladstone 2nd Ave to 3rd Ave	5	2	Gladstone	2nd Ave	3rd Ave
Sewer	Procurement	Repair	DWS-916	Gladstone Woodward to 2nd Ave	5	266	Gladstone	Woodward	2nd Ave
Sewer	Construction	Replace	DWS-907	Glastonbury Rd McNichols Rd to Grove St	1	495	Glastonbury Rd	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Glastonbury Rd Grove St to Verne Ave	1	669	Glastonbury Rd	Grove St	Verne Ave
Sewer	Construction	Replace	DWS-907	Glastonbury Rd Puritan Ave to Florence St	1	27	Glastonbury Rd	Puritan Ave	Florence St
Sewer	Construction	Replace	DWS-907	Glastonbury Rd McNichols Rd to Grove St	1	495	Glastonbury Rd	McNichols Rd	Grove St
Sewer	Construction	Replace	DWS-907	Grand River Alley Bretton Dr to Outer Dr	1	325	Grand River Alley	Bretton Dr	Outer Dr
Sewer	Construction	-	DWS-907	Grand River Alley Bretton Dr to Outer Dr	1		Grand River Alley	Bretton Dr	Outer Dr
Sewer	Construction	•	DWS-907	Grand River Alley Outer Dr to Warwick St	1	745	Grand River Alley	Outer Dr	Warwick St
Sewer	Construction	•	DWS-907	Grand River Alley Avon Rd to Glastonbury Ave	1	10	Grand River Alley	Avon Rd	Glastonbury Ave
Sewer	Construction	-	DWS-907	Grand River Alley Glastonbury Ave to Kentford St	1	365	Grand River Alley	Glastonbury Ave	Kentford St
Sewer	Construction	Repair	DWS-907	Grand River Alley Kentford St to Bretton Dr	1	139	Grand River Alley	Kentford St	Bretton Dr
Water	Procurement	•	WS-715	Perpendicular to Grand River Ave 183' South of Glastonbury Ave	1	66	Grand River Ave	183' from Glastonbury	<null></null>
Sewer	Construction	-	DWS-907	Grand River Ave Warwick St to Avon Rd	1	706	Grand River Ave	Warwick St	Avon Rd
Water	Construction	•	WS-714	Grand River Avenue Fenkell to McNichols	1	14,837	Grand River Avenue	Fenkell	McNichols
Water	Construction	•	WS-714	Grand River Avenue Maren to Southfield HWY	1	14,837	Grand River Avenue	Maren	Southfield HWY
Water	Procurement	_	CS-1909 DWSD	Grandville Joy Road to Belton	7		Grandville	Joy Road	Belton
Water	Procurement	_	CS-1909 DWSD	Gratiot (M-3) Seven Mile to Eight Mile	4		Gratiot (M-3)	Seven Mile	Eight Mile
Sewer		Repair	DWS-908	Gravier Bluehill to Cadieux	4		Gravier	Bluehill	Cadieux
Water	Design	Repair	WS-711	Greenfield West Chicago to Warren	7		Greenfield Road	West Chicago	Warren
Water	Design	Repair	WS-711	Greenview Warren to Paul	7	,	Greenview	Warren	Paul
Water	Procurement	Repair	CS-1909 DWSD	Greenview Sawyer to Tireman	1		Greenview	Sawyer	Tireman
Water		Repair	CS-1909 DWSD	Greenview Kirkwood to Dayton	1		Greenview	Kirkwood	Dayton
Water	Procurement	_	CS-1909 DWSD	Greenview Chalfonte to Fenkell	1		Greenview	Chalfonte	Fenkell
Sewer	Construction	•	DWS-907	Greenview Ave Florence St to Puritan Ave	1		Greenview Ave	Florence St	Puritan Ave
Sewer	Construction	-	DWS-907	Grove St Evergreen Rd to Plainview Ave	1		Grove St	Evergreen Rd	Plainview Ave
•1		F			-	10		_ · 0- 3 tm 2 tm	···································

Type	Phase	Activity	Project ID	Location	Districts	Length	Street	Street From	Street To
Sewer	Construction	Repair	DWS-907	Grove St Evergreen Rd to Plainview Ave	1	10	Grove St	Evergreen Rd	Plainview Ave
Sewer	Construction	Repair	DWS-907	Grove St Westmoreland Rd to Plainview Ave	1	346	Grove St	Westmoreland Rd	Plainview Ave
Sewer	Construction	Repair	DWS-907	Grove St Edinborough Rd to Huntington Rd	1	293	Grove St	Edinborough Rd	Huntington Rd
Sewer	Construction	-	DWS-907	Grove St Westmoreland Rd to Edinborough Rd	1	215	Grove St	Westmoreland Rd	Edinborough Rd
Sewer	Construction	Repair	DWS-907	Grove St Outer Dr to Huntington Rd	1	190	Grove St	Outer Dr	Huntington Rd
Water	Construction	Replace	WS-712	Guilford St Harper St southeast to Chandler Park Dr	4	2,999	Guildford St	Harper St southeast	Chandler Park Dr
Sewer	Construction	Repair	DWS-908	Guilford Warren to Munich	4	53	Guilford	Warren	Munich
Sewer	Construction	Repair	DWS-908	Guilford Windsor to Mack	4	552	Guilford	Windsor	Mack
Sewer	Construction	-	DWS-908	Guilford Berden to Linville	4		Guilford	Berden	Linville
Sewer	Construction	_	DWS-908	Guilford Chandler Park to Southampton	4	373	Guilford	Chandler Park	Southampton
Sewer	Construction	Repair	DWS-908	Guilford Harper to Linville	4	358	Guilford	Harper	Linville
Sewer	Construction	-	DWS-908	Guilford Linville to Chandler Park	4		Guilford	Linville	Chandler Park
Water	Construction	Replace	WS-712	Guilford St alley southeast to Warren Ave	4		Guilford St	alley southeast	Warren Ave
Water	Construction	Replace	WS-712	Guilford St alley southeast to Warren Ave	4		Guilford St	alley southeast	Warren Ave
Water	Design	Replace	WS-713	Harbor Island Lakewood to dead end (before Alter)	4	_ ′	Harbor Island	Lakewood	Alter Rd
Water	Procurement	_	CS-1909 DWSD	Harlow Puritan to Verne	1		Harlow	Puritan	Verne
Sewer	Construction	_	DWS-908	Harper Woodhall to Oldtown	4		Harper	Woodhall	Oldtown
Water	Procurement	•	CS-1909 DWSD	Hayes Seven Mile to Houston-Whitier	4	5,319	•	Seven Mile	Houston-Whitier
Water	Procurement	Repair	CS-1909 DWSD	Hayes Elmdale to Harper Avenue	4	2,055		Elmdale	Harper Avenue
Water	Construction	-	WS-712	Hereford St Minerva St southeast to Chandler Park Dr	4	,	Hereford St	Minerva St southeast	Chandler Park Dr
Water	Construction	•	WS-712	Hillcrest St Rolandale St southeast to Mack Ave	4		Hillcrest St	Rolandale St southeast	Mack Ave
Sewer	Construction	-	DWS-907	Huntington Rd Bretton Dr to Bretton Dr	1		Huntington Rd	Bretton Dr	Bretton Dr
Sewer	Construction	-	DWS-907	Huntington Rd Florence St to Bretton Dr	1		Huntington Rd	Florence St	Bretton Dr
Sewer	Construction	-	DWS-907	Huntington Rd Grove St to Grove St	1		Huntington Rd	Grove St	Grove St
Sewer	Construction	-	DWS-907	Huntington St Grove St to Verne Ave	1		Huntington St	Grove St	Verne Ave
Water	Design	Repair	WS-711	Jefferson Ave (Both Sides) Mt. Elliott to Beafauit	5		Jefferson Ave (Both Sides)	Mt. Elliott	Beafauit
Water	Design	Repair	WS-711	Jefferson Ave (N Side) I-375 Svc Dr to Orleans	5		Jefferson Ave (N Side)	I-375 Svc Dr	Orleans
Water		Repair	CS-1909 DWSD	Jefferson Ave. W. 15th St. to Vermont St.	6		Jefferson Ave. W.	15th St.	Vermont St.
Water	Procurement	_	CS-1909 DWSD	Jefferson Ave. W. Vermont St. to Rosa Park Blvd.	6		Jefferson Ave. W.	Vermont St.	Rosa Park Blvd.
Water	Procurement	•	CS-1909 DWSD	Jefferson Ave. W. (N) Shelby St. to Woodward	6		Jefferson Ave. W. (N)	Shelby St.	Woodward
Water	Procurement	1	CS-1909 DWSD	Jefferson Ave. W. (S) Civic Center Dr. to Woodward Ave.	6		Jefferson Ave. W. (S)	Civic Center Dr.	Woodward Ave.
Sewer	Procurement	-	DWS-916	John C Lode FWY Easement N. of Gladstone to Delaware	5	,	John C Lode FWY		Delaware
Water	Procurement	•	CS-1909 DWSD	Joy Road Wyoming to Livernois	7		Joy Road	Wyoming	Livernois
Water	Design	Repair	WS-710	Kelly Glenwood to Eastwood	7	1,424	•	Glenwood	Eastwood
Sewer		Repair	DWS-908	Kingsville Edgefield to Tyrone	4		Kingsville	Edgefield	Tyrone
Water	Design	Replace	WS-713	Klenk St. Alter to dead end	4		Klenk St.	Alter	Riverside Blvd
Water	Design	NEW PIPE	WS-713	Klenk St. Dead end across channel to Riverside Blvd	4		Klenk St.	Riverside Blvd	Dead End West
Water	Construction	-	WS-712	Lafontaine St Canyon St to Mack Ave	4		Lafontaine	Canyon St	Mack Ave
Water	Procurement	•	WS-715	Lahser Rd Kessler to Puritan  Lahser Rd McNichols Rd to Grove	1		Lahser Rd Lahser Rd	Kessler McNichols Rd	Puritan
Water Water	Procurement Design	Lining	WS-715 WS-713	Lakewood Riverside Blvd to Scripps	1		Lakewood	Riverside Blvd	Grove
Water	Design	Upsize Upsize	WS-713 WS-713	Lakewood Scripps to Avondale	4		Lakewood		Scripps Avondale
Water	Design	Upsize	WS-713 WS-713	Lakewood Essex to Avondale  Lakewood Essex to Avondale	4		Lakewood	Scripps Essex	Avondale
Water	Ū	Repair	CS-1909 DWSD	Lamphere Sawyer to Majestic	7		Lamphere	Sawyer	Majestic
Water	Procurement	_	WS-715	Lamphere Verne to Puritan	1		Lamphere	Verne	Puritan
Sewer	Construction	_	DWS-907	Lancashire St Outer Dr to Warwick St	1		Lancashire St	Outer Dr	Warwick St
Sewer	Construction	-	DWS-907	Lancashire St. Outer Dr to Warwick St.  Lancashire St. Outer Dr to Bretton Dr	1		Lancashire St	Outer Dr	Bretton Dr
Sewer	Construction	_	DWS-907	Lancashire St Warwick St to Avon Rd	1		Lancashire St	Warwick St	Avon Rd
Water	Construction	•	WS-712	Lannoo St Linville St to Chandler Park Dr	$\Delta$		Lannoo St	Linville St	Chandler Park Dr
Water	Construction	-	WS-712 WS-712	Lannoo St Canyon Ave to Linville St	$rac{ au}{arDelta}$		Lannoo St	Canyon Ave	Linville St
Water	Design	Replace	WS-712 WS-713	Lenox Korte to dead-end south of Scripps	4		Lenox	Korte	Scripps
Water	Procurement	_	CS-1909 DWSD	Lindsay Curtis to Clarita	2.		Lindsay	Curtis	Clarita
Water	Construction	-	WS-712	Linville Moross Rd. to Kingsville St.	4		Linville	Moross Rd.	Kingsville St.
Water	Procurement	_	CS-1909 DWSD	Lothrop Rd. 3rd Street to 2nd Street	5		Lothrop Rd.	3rd Street	2nd Street
Water	Procurement	-	CS-1909 DWSD	Lothrop Rd. 2nd Street to Woodward	5		Lothrop Rd.	2nd Street	Woodward
Sewer	Construction	•	DWS-908	Mack Farmbrook to Radnor	4		Mack	Farmbrook	Radnor
~ > •1		г			•	213	··		<del></del>

Type	Phase	Activity	Project ID	Location	Districts	Length	Street	Street From	Street To
Water	Construction	Replace	WS-712	Mack Ave Moross Rd to Allard Ave	4	639	Mack Ave	Moross Rd	Allard Ave
Water	Construction	Replace	WS-712	Mack Ave Neff Ave northeast towards Hereford St	4	128	Mack Ave	Neff Ave northeast	Hereford St
Water	Design	Replace	WS-713	Manistique Essex to Scripps	4	2,585	Manistique	Essex	Scripps
Water	Procurement	-	CS-1909 DWSD	Manor Joy to Tireman	7		Manor	Joy	Tireman
Water	Procurement	-	CS-1909 DWSD	Mansfield Thatcher to Curtis	2	695	Mansfield	Thatcher	Curtis
Water	Procurement	-	CS-1909 DWSD	Mansfield Capital to Wadsworth	1	848	Mansfield	Capital	Wadsworth
Water	Construction	-	WS-707	Margareta Codding to Shiawassee	1		Margareta	Codding	Shiawassee
Water	Design	Replace	WS-713	Marlborough Freud to Jefferson	4		Marlborough	Freud	Jefferson
Water	Procurement	-	CS-1909 DWSD	McGraw Cecil to Warren W.	6		McGraw	Cecil	Warren W.
Water	Construction	-	WS-706	McNichols Schaefer to James Couzens	2	1,918	McNichols	Schaefer	James Couzens
Sewer	Construction	-	DWS-907	Midland Rd Rosemont Ave to Ashton Rd	1	1,279	Midland Rd	Rosemont Ave	Ashton Rd
Sewer	Construction	-	DWS-908	Minneapolis Guilford to Cadieux	4		Minneapolis	Guilford	Cadieux
Water	Procurement	-	WS-715	Minock St Grand River Avenue to Fenkell St	1		Minock St	Grand River Avenue	Fenkell St
Water	Procurement	_	CS-1909 DWSD	Montrose Schoolcraft to Grand River	1		Montrose	Schoolcraft	Grand River
Sewer	Construction	-	DWS-908	Moross Cheshire to Mallina	4	253	Moross	Cheshire	Mallina
Sewer	Construction	-	DWS-908	Moross Edsel Ford Hwy to Edgefield	4		Moross	Edsel Ford Hwy	Edgefield
Water	Construction	-	WS-712	Moross Rd Edsel Ford Service Dr southeast to Alstead St	4		Moross Rd	Edsel Ford Service Dr south	•
Water	Design	Replace	WS-713	Navahoe Essex to Avondale	4		Navahoe	Essex	Avondale
Water	Design	Repair	WS-711	NB Southfield Fwy Service Drive 7 Mile to Pembroke	1		NB Southfield Fwy Service Dri		Pembroke
Sewer	•	Repair	DWS-908	Neff Minvera to Berden	4		Neff	Minvera	Berden
Sewer	Construction	-	DWS-908	Neff Berden to Chandler Park	4		Neff	Berden	Chandler Park
Sewer	Construction	-	DWS-908	Neff Warren to Munich	4		Neff	Warren	Munich
Sewer	Construction	-	DWS-908	Neff Southampton to Warren	4		Neff	Southampton	Warren
Sewer	Construction	-	DWS-908	Neff Chandler Park to Southampton	4		Neff	Chandler Park	Southampton
Sewer	Construction	-	DWS-908	Neff Munich to Waveney	4		Neff	Munich	Waveney
Water	Construction	_	WS-712	New York St Cadieux Rd northeast to Guilford St	4		New York	Cadieux Rd northeast	Guilford St
Sewer	Construction	-	DWS-908	New York Cadieux to Guilford	4		New York	Cadieux	Guilford
Sewer	Construction	-	DWS-908	New York Cadieux to Guilford	4		New York	Cadieux	Guilford
Water	Design	Replace	WS-713	Newport dead end to Scripps (added new valve)	4		Newport	Scripps	Dead End South
Water	Design	Replace	WS-713	Newport Avondale to Essex	4		Newport	Avondale	Essex
Water	_	Repair	CS-1909 DWSD	Oakfield Puritan to Verne	2		Oakfield	Puritan	Verne
Water	Procurement	_	PC-801A	Oakman Joy to Tireman	7		Oakman	Joy	Tireman
Sewer	Construction	-	DWS-908	Oldtown Linville to Harper	1	*	Oldtown	•	Harper
Sewer	Construction	=	DWS-908	Oldtown Chandler Park to Southampton	<del>1</del> Δ		Oldtown	Chandler Park	Southampton
Water	Construction	-	WS-712	Oldtown St Chandler Park Dr southeast to Southampton St	<del>1</del> Δ		Oldtown St	Chandler Park Dr southeast	-
Sewer	Construction		DWS-908	Ontario Cadieux to Guilford	<del>1</del> Δ		Ontario	Cadieux	Guilford
Sewer	Construction	_	DWS-908	Ontario Cadieux to Guilford	1		Ontario	Cadieux	Guilford
Water	Construction	-	WS-712	Opal Canyon St. to Mack Ave	1		Opal	Canyon St.	Mack Ave
Water	Procurement	_	CS-1909 DWSD	Orangelawn Burt to Westwood	7		Orangelawn	Burt	Westwood
Sewer	Construction	-	DWS-907	Outer Dr McNichols Rd to Grove St	1		Outer Dr	McNichols Rd	Grove St
Sewer	Construction	-	DWS-907	Outer Dr Grand River Ave to Lancashier St	1		Outer Dr	Grand River Ave	Lancashier St
Sewer	Construction	-	DWS-907	Outer Dr Bretton Dr to Gainsborough Rd	1		Outer Dr	Bretton Dr	Gainsborough Rd
Sewer	Construction	_	DWS-907	Outer Dr Gainsborough Rd to Lancashire St	1		Outer Dr	Gainsborough Rd	Lancashire St
Sewer	Construction	-	DWS-907	Outer Dr Grove St to Verne Ave	1		Outer Dr	Grove St	Verne Ave
Water	Procurement	_	CS-1909 DWSD	Pallister Lodge Service Dr. to 3rd	1		Pallister	Lodge Service Dr.	3rd
Sewer	Procurement	_	DWS-916	Pallister Woodward to 2nd Ave	5		Pallister	Woodward	2nd Ave
Sewer	Procurement	-	DWS-916	Easement S. Pallister Woodward to John C Lodge FWY	5		Pallister	Woodward	John C Lodge FWY
		-	WS-713	Newport dead end to Park	J 1	1,728			•
Water Water	Design Procurement	Loop Lining	WS-715 WS-715	Patton St Grand River Ave to Pilgrim	1		Patton St	Lenox Grand River Ave	Newport Pilgrim
Water		_	WS-713 WS-707	Pembroke James Couzens to Biltmore	1 1	,	Pembroke	James Couzens	Biltmore
	Construction Procurement	_	WS-707 CS-1909 DWSD	Penrod Eaton to Lyndon	1		Penrod		
Water		-	WS-715	•	1		Pernod	Eaton	Lyndon
Water	Procurement	-	WS-713 WS-713	Pernod Eaton to Lyndon  Philip Essay to Saripps	1 1		Philip	Eaton Essex	Lyndon
Water	Design Progurament	Replace	WS-713 CS-1909 DWSD	Philip Essex to Scripps  Piercon Polton to Tiroman	7		Pierson		Scripps
Water	Procurement	_		Pierson Belton to Tireman  Pierson Senta Clara to McNighele	1			Belton Sonto Cloro	Tireman MeNichels
Water	Procurement	-	CS-1909 DWSD	Pierson Santa Clara to McNichols  Pierson St Grand Piver Ave to Pilgrim	1		Pierson St	Santa Clara	McNichols Dilgrim
Water	Procurement	кергасе	WS-715	Pierson St Grand River Ave to Pilgrim	1	1,5/1	Pierson St	Grand River Ave	Pilgrim

Type	Phase	Activity	Project ID	Location	Districts	Length	Street	Street From	Street To
Water	Procurement	Repair	CS-1909 DWSD	Pinehurst Joy to Tireman	7	2,664	Pinehurst	Joy	Tireman
Sewer	Procurement	Repair	DWS-916	Pingree 2nd Ave to 2nd Ave	5	3	Pingree	2nd Ave	2nd Ave
Sewer	Procurement	Repair	DWS-916	Pingree Woodward Easement W. of Woodward	5	255	Pingree	Woodward	Easement W. of Woodward
Water	Design	Replace	WS-713	Piper Scripps to Averhill (to new valve)	4	1,894	Piper	Scripps	Averhill
Water	Design	Lining	WS-713	Piper dead end to Scripps (added new valve)	4	409	Piper	Scripps	Dead End South
Sewer	Construction	Repair	DWS-907	Plainview Ave Florence St to Florence St	1	32	Plainview Ave	Florence St	Florence St
Sewer	Construction	Repair	DWS-907	Plainview Ave Verne Ave to Florence St	1	10	Plainview Ave	Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Plainview Ave Grove St to Verne Ave	1	625	Plainview Ave	Grove St	Verne Ave
Sewer	Construction	•	DWS-907	Plainview Ave McNichols Rd to McNichols Rd	1	30	Plainview Ave	McNichols Rd	McNichols Rd
Sewer	Construction	-	DWS-907	Plainview Ave Grove St to Grove St	1	29	Plainview Ave	Grove St	Grove St
Sewer	Construction	•	DWS-907	Plainview Ave Verne Ave to Verne Ave	1	56	Plainview Ave	Verne Ave	Verne Ave
Sewer	Construction	•	DWS-907	Planview Ave Florence St to Verne St	1	544	Planview Ave	Florence St	Verne St
Water	Procurement	-	CS-1909 DWSD	Plymouth Redford City Limit to Evergreen	7	8,184	Plymouth	Redford City Limit	Evergreen
Water	Procurement	•	CS-1909 DWSD	Plymouth Schaefer to Wyoming	7		Plymouth	Schaefer	Wyoming
Water	Procurement	•	CS-1909 DWSD	Prevost Midland to Pilgrim	1		Prevost	Midland	Pilgrim
Water	Procurement	-	WS-715	Puritan Beaverland to Chatham	1		Puritan	Beaverland	Chatham
Water	Construction	•	DWS-907	Puritan Ave Glastonbury Ave east to Rosemont Ave	1		Puritan Ave	Glastonbury Ave East	Rosemont Ave
Sewer	Construction	•	DWS-907	Puritan Ave Glastonbury Ave to Rosemont Ave			Puritan Ave	Glastonbury Ave	Rosemont Ave
Sewer	Construction	-	DWS-907	Puritan Ave Rosemont Ave to Ashton Rd	1		Puritan Ave	Rosemont Ave	Ashton Rd
Water	Procurement	-	WS-715	Puritan St Blackstone to Burt Rd	1 ^		Puritan St	Blackstone	Burt Rd
Water	Construction	•	WS-712	Radnor St Chester St southeast to Chandler Park Dr	4		Radnor	Chester St southeast	Chandler Park Dr
Water	Construction	-	WS-712	Radnor Warren Ave to Frankfort St.	4		Radnor	Warren Ave	Frankfort St.
Sewer	Construction	•	DWS-908	Radnor Southampton to Warren	4			Southampton	Warren
Sewer	Construction	•	DWS-908	Radnor Warren to Mack	4	,	Radnor	Warren	Mack
Water	Construction	-	WS-712	Radnor St. Frankfort St southeast to Mack Ave	4		Radnor St	Frankfort St southeast	Mack Ave
Water	Construction	-	WS-712	Radnor St. Frankfort St southeast to Mack Ave	4		Radnor St	Frankfort St southeast	Mack Ave
Water	Construction	-	WS-712	Radnor St Chandler Park Dr to Southampton St	4		Radnor St	Chandler Park Dr	Southampton St
Water	Procurement	-	WS-715	Ridge Rd Riverdale to Florence		,	Ridge Rd	Riverdale	Florence
Water	Construction	-	WS-715 WS-706	Robson Ave. Curtis Ave. to W. Seven Mile	1		Robson Ave.	Curtis Ave.	W. Seven Mile
Water	Construction	-	WS-712	Rolandale St. Moross Rd. to Kingsville St.	1		Rolandal	Moross Rd.	Kingsville St.
Water	Construction	-	WS-712 WS-712	Rolandale St. Hillcrest St to Moross Rd	4		Rolandale	Hillcrest St	Moross Rd
Water	Procurement	-	CS-1909 DWSD	Rosemont Van Buren to Constance	7		Rosemont	Van Buren	Constance
Water	Procurement	-	CS-1909 DWSD	Rosemont Schoolcraft to Dead End	1		Rosemont	Schoolcraft	Dead End
Water	Procurement		CS-1909 DWSD	Rosemont Curtis to Margareta	1	,	Rosemont	Curtis	Margareta
Water	Procurement	-	CS-1909 DWSD	Rosemont Fargo to Hessel	1		Rosemont	Fargo	Hessel
Water	Construction	-	DWS-907	Rosemont Ave Midland St north to Puritan Ave	1		Rosemont Ave	Midland St north	Puritan Ave
~	Construction	-	DWS-907	Rosemont Ave Verne Ave to Florence St	1		Rosemont Ave	Verne Ave	Florence St
Sewer Sewer	Construction	-	DWS-907	Rosemont Ave Pilgrim St to Puritan Ave	1		Rosemont Ave	Pilgrim St	Puritan Ave
~	Construction	_	DWS-907	Rosemont Ave Florence St to Puritan Ave	1		Rosemont Ave	Florence St	Puritan Ave
Sewer	Construction	-	DWS-907	Rosemont Ave Midland St to Bretton Dr	1		Rosemont Ave	Midland St	Bretton Dr
Sewer Water	Procurement	-	CS-1909 DWSD	Rutherford Keeler to Puritan	1		Rutherford	Keeler	Puritan
~		-	DWS-907	Scardale St Glastonbury Ave to Glastonbury Ave	1		Scardale St		
Sewer	Construction	-	DWS-907	·	1		Scarsdale St	Glastonbury Ave Avon Rd	Glastonbury Ave
Sewer	Construction Procurement	-	CS-1909 DWSD	Scarsdale St Avon Rd to Glastonbury Ave Schaefer Joy Road to Tireman	7		Schaefer St	Joy Road	Glastonbury Ave Tireman
Water		-	CS-1909 DWSD CS-1909 DWSD	•	7		Schaefer NB/SB	•	830 feet south of Westfield
Water	Procurement	-		Schaefer NB/SB W. Chicago to 830 feet south of Westfield	1			W. Chicago	
Sewer	Construction	-	DWS-908	School Lot Frankfort to Cadieux	4		School Lot	Frankfort	Cadieux
Sewer	Construction	-	DWS-908	School lot (Tennis courts) Guilford to Access Road	7		School lot (Tennis courts)	Guilford	Access Road
Water	Design	Repair	WS-710	Schoolcraft Asbury Park to Greenfield	7		Schoolcraft	Asbury Park	Greenfield
Water	Design	Repair	WS-710	Schoolcraft Greenfield to Grand River	1		Schoolcraft	Greenfield	Grand River
Water	Procurement	Repair	CS-1909 DWSD	Schoolcraft Asbury Park to Mettetal	1		Schoolcraft	Asbury Park	Mettetal
Water	Design	Replace	WS-713	Scripps Ashland to Lakewood	4		Scripps	Ashland	Lakewood
Water	Design	Lining	WS-713	Scripps Lakewood to Lenox	4		Scripps	Lakewood	Lenox
Water			CS-1909 DWSD	Seven Mile John R. to Dequindre	2		Seven Mile	John R.	Dequindre
Water	Procurement	-	CS-1909 DWSD	Seven Mile Dequindre to Ryan	3		Seven Mile	Dequindre	Ryan
Water	Procurement	-	CS-1909 DWSD	Seven Mile Ryan to Mound	3		Seven Mile	Ryan	Mound
Water	Procurement	Repair	CS-1909 DWSD	Seven Mile Mound to Van Dyke	3	5,242	Seven Mile	Mound	Van Dyke

Type	Phase	Activity	Project ID	Location	Districts	Length	Street	Street From	Street To
Sewer	Procurement	Repair	DWS-916	Seward Woodward to Woodward	5	3	Seward	Woodward	Woodward
Water	Procurement	Replace	WS-718	Seward St 2nd Ave to 3rd St	5	978	Seward St	2nd Ave	3rd St
Sewer	Construction	Repair	DWS-907	Shaftsbury Ave Grove St to Verne Ave	1	20	Shaftsbury Ave	Grove St	Verne Ave
Sewer	Construction	Repair	DWS-907	Shaftsbury Ave McNichols Rd to Grove St	1	521	Shaftsbury Ave	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-908	Sioux Guilford to Cadieux	4	52	sioux	Guilford	Cadieux
Sewer	Construction	Replace	DWS-908	Sioux Guilford to Cadieux	4		sioux	Guilford	Cadieux
Water	Construction	Replace	WS-712	Sioux St Cadieux Rd northeast to Guilford St	4	639	Sioux St	Cadieux Rd northeast	Guilford St
Water	Procurement	Repair	CS-1909 DWSD	Sorrento Joy to Tireman	7	2,719	Sorrento	Joy	Tireman
Water	Construction	Replace	WS-712	Southampton St Oldtown St northeast to Bluehill St	4	273	Southampton	Oldtown St NorthEast	Bluehill St
Water	Procurement	Replace	WS-715	Southfield FWY Grand River Ave to Lyndon St	1	2,558	Southfield FWY	Grand River Ave	Lyndon St
Sewer	Construction	Repair	DWS-907	Southfield FWY Verne Ave to Florence St	1	639	Southfield FWY	Verne Ave	Florence St
Sewer	Construction	Repair	DWS-907	Southfield FWY McNichols Rd to Grove St	1	10	Southfield FWY	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Southfield FWY Puritan Ave to Pilgrim St	1	1,226	Southfield FWY	Puritan Ave	Pilgrim St
Sewer	Construction	Repair	DWS-907	Southfield FWY Florence St to Florence St	1	12	Southfield FWY	Florence St	Florence St
Water	Procurement	Repair	CS-1909 DWSD	Southfield Svc Drive North Fenkell to Puritan	1	649	Southfield Svc Drive North	Fenkell	Puritan
Water	Procurement	Repair	CS-1909 DWSD	Southfield Svc Drive North Schoolcraft to Grand River	7	5,067	Southfield Svc Drive North	Schoolcraft	Grand River
Water	Design	Replace	WS-716	St Antoine St Wilkens to Winder	5	1,068	St Antoine St	Wilkens	Winder
Sewer	Construction	Repair	DWS-907	Stahelin Ave Verne Ave to McNichols Rd	1	311	Stahelin Ave	Verne Ave	McNichols Rd
Water	Construction	Repair	WS-706	Stansbury Ave. Outer Drive to Curtis	1	1,207	Stansbury Ave.	Outer Drive	Curtis
Water	Procurement	Repair	CS-1909 DWSD	Steel Joy to Mackenzie	7	891	Steel	Joy	Mackenzie
Sewer	Construction	Repair	DWS-907	Sunderland Rd Florence St to Puritan Ave	1	684	Sunderland Rd	Florence St	Puritan Ave
Sewer	Construction	Repair	DWS-907	Sunderland Rd Florence St to Puritan Ave	1	687	Sunderland Rd	Florence St	Puritan Ave
Water	Procurement	Repair	CS-1909 DWSD	Sylvan McKinley to Vinewood	6	466	Sylvan	McKinley	Vinewood
Sewer	Procurement	Repair	DWS-916	Taylor 2nd Ave to 3rd Ave	5	14	Taylor	2nd Ave	3rd Ave
Water	Procurement	Repair	CS-1909 DWSD	Theisen Mendota Joy to Tireman	7	2,639	Theisen Mendota	Joy	Tireman
Water	Construction	Repair	WS-706	Tireman Greenfield to Hubbell	7	2,631	Tireman	Greenfield	Hubbell
Water	Construction	Repair	WS-712	University Place Munich Ave. to Mack Ave.	4	1,464	University	Munich Ave.	Mack Ave.
Sewer	Construction	Repair	DWS-908	University Chandler Park to Southampton	4	208	University	Chandler Park	Southampton
Water	Procurement	Repair	CS-1909 DWSD	Vaughan Belton to Constance	7	652	Vaughan	Belton	Constance
Water	Procurement	Repair	CS-1909 DWSD	Vaughn Sawyer to Tireman	7	1,288	Vaughn	Sawyer	Tireman
Water	Procurement	Replace	WS-715	Verne Dolphin to Lahser	1	550	Verne	Dolphin	Lahser
Sewer	Construction	Repair	DWS-907	Verne Ave Huntington Rd to Outer Dr	1	54	Verne Ave	Huntington Rd	Outer Dr
Sewer	Construction	Repair	DWS-907	Verne Ave Glastonbury Rd to Glastonbury Rd	1	18	Verne Ave	Glastonbury Rd	Glastonbury Rd
Sewer	Construction	Repair	DWS-907	Verne Ave Plainview Ave to Westmoreland Rd	1	370	Verne Ave	Plainview Ave	Westmoreland Rd
Sewer	Construction	Repair	DWS-907	Verne Ave Westmoreland Rd to Edinborough Rd	1	522	Verne Ave	Westmoreland Rd	Edinborough Rd
Sewer	Construction	Repair	DWS-907	Verne Ave Evergreen Rd to Plainview Ave	1	20	Verne Ave	Evergreen Rd	Plainview Ave
Sewer	Construction	Repair	DWS-907	Verne Ave Shaftsbury Ave to Sunderland Rd	1	380	Verne Ave	Shaftsbury Ave	Sunderland Rd
Sewer	Construction	Repair	DWS-907	Verne Ave Outer Dr to Shaftsbury Ave	1		Verne Ave	Outer Dr	Shaftsbury Ave
Water	Procurement	Replace	WS-718	Virginia Park St Woodward Ave to John Lodge Fwy	5	2,473	Virginia Park St	Woodward Ave	John Lodge Fwy
Water	Procurement	Replace	WS-718	Virginia Park St Woodward Ave to John Lodge Fwy	5	2,516	Virginia Park St	Woodward Ave	John Lodge Fwy
Water	Procurement	Repair	CS-1909 DWSD	Virginia Park St.(S) John C Lodge to 3rd Street	5		Virginia Park St.(S)	John C Lodge	3rd Street
Water	Procurement	-	CS-1909 DWSD	W. Chicago Stout to Evergreen	7	1,018	W. Chicago	Stout	Evergreen
Water	Procurement	-	CS-1909 DWSD	W. Parkway Tireman to Sawyer	7		W. Parkway	Tireman	Sawyer
Water	Procurement	Repair	CS-1909 DWSD	Ward Joy to Tireman	7		Ward	Joy	Tireman
Water	Construction	Repair	WS-706	Warren Parkland to Heyden	7		Warren	Parkland	Heyden
Water	Design	Repair	WS-710	Warren Evergreen to Southfield	7		Warren	Evergreen	Southfield
Water	Design	Repair	WS-710	Warren Heyden to Evergreen	7		Warren	Heyden	Evergreen
Sewer	Construction	Repair	DWS-908	Warren Guilford to Cadieux	4		Warren	Guilford	Cadieux
Sewer	Construction	-	DWS-908	Warren Guilford to Cadieux	4		Warren	Guilford	Cadieux
Water	Construction	Repair	WS-712	Warren Ave Cadieux Ave to Guilford St	4		Warren Ave	Cadieux Ave	Guilford St
Water	Construction	-	WS-712	Warren Ave (north) Guilford St northeast to Woodhall St	4		Warren Ave	Guilford St northeast	Woodhall St
Water	Construction	_	WS-712	Warren Ave (north) Farmbrook St northeast to Canyon St	4		Warren Ave (north)	Farmbrook St northeast	Canyon St
Water	Construction	-	WS-712	Warren Ave (south) Farmbrook St northeast to Canyon St	4		Warren Ave (south)	Farmbrook St northeast	Canyon St
Water	Construction	-	WS-712	Warren Ave. Cadieux Rd. to Guilford St.	4		Warren Ave.	Cadieux Rd.	Guilford St.
Sewer	Construction	-	DWS-907	Warwick St Bretton Dr to Gainsborough Rd	1		Warwick St	Bretton Dr	Gainsborough Rd
Sewer	Construction	Repair	DWS-907	Warwick St Puritan Ave to Bretton Dr	1	10	Warwick St	Puritan Ave	Bretton Dr

Type	Phase	Activity	Project ID	Location	Districts	Length	Street	Street From	Street To
Sewer	Construction	Replace	DWS-907	Warwick St McNichols Rd to Grove St	1	610	Warwick St	McNichols Rd	Grove St
Sewer	Construction	Repair	DWS-907	Warwick St Grove St to Verne Ave	1	674	Warwick St	Grove St	Verne Ave
Water	Construction	Replace	DWS-907	Warwick St Florence St north to McNichols Rd	1	3,648	Warwick St fr	Florence St north	McNichols Rd
Sewer	Procurement	Repair	DWS-916	Watson Chrysler to Beaubien	5	81	Watson	Chrysler	Beaubien
Water	Construction	Replace	WS-712	Waveney St Cadieux Rd northeast to Guilford St	4	663	Waveney St	Cadieux Rd northeast	Guilford St
Water	Design	Repair	WS-710	West Chicago City Limits to Brammel	7	848	West Chicago	City Limits	Brammel
Water	Procurement	Repair	CS-1909 DWSD	West Chicago West Outer Drive to Hazelton/City Limits	7	1,613	West Chicago	West Outer Drive	Hazelton/City Limits
Water	Procurement	Repair	CS-1909 DWSD	West Grand Blvd Magnolia to McGraw	6	5,195	West Grand Blvd	Magnolia	McGraw
Water	Procurement	Repair	CS-1909 DWSD	West Grand Blvd McGraw to Linwood	6	6,265	West Grand Blvd	McGraw	Linwood
Water	Procurement	Repair	CS-1909 DWSD	West Grand Blvd W. Jefferson Ave. to Vernor	6	4,307	West Grand Blvd	W. Jefferson Ave.	Vernor
Water	Procurement	Repair	CS-1909 DWSD	West Grand Blvd Vernor to Magnolia	6	6,289	West Grand Blvd	Vernor	Magnolia
Water	Procurement	Repair	CS-1909 DWSD	West Grand Blvd Linwood to Lodge Frwy	5	5,484	West Grand Blvd	Linwood	Lodge Frwy
Water	Procurement	Repair	CS-1909 DWSD	West Outer Dr. Fenkell to Evergreen	1	2,121	West Outer Dr.	Fenkell	Evergreen
Water	Design	Repair	WS-710	West Outer Drive Joy Road to Warren	7	6,936	West Outer Drive	Joy Road	Warren
Water	Design	Repair	WS-711	West Parkway Tireman to Plymouth	7	8,265	West Parkway	Tireman	Plymouth
Water	Procurement	Lining	WS-715	Westbrook St Verne to Puritan	1	1,285	Westbrook St	Verne	Puritan
Sewer	Construction	Repair	DWS-907	Westmoreland Rd Grove St to Verne Ave	1	631	Westmoreland Rd	Grove St	Verne Ave
Sewer	Construction	Repair	DWS-907	Westmoreland Rd Florence St to Florence St	1	10	Westmoreland Rd	Florence St	Florence St
Sewer	Construction	Replace	DWS-907	Westmoreland Rd Grove St to Grove St	1	24	Westmoreland Rd	Grove St	Grove St
Sewer	Construction	Repair	DWS-907	Westmoreland Rd Grove St to McNichols Rd	1	316	Westmoreland Rd	Grove St	McNichols Rd
Sewer	Construction	Repair	DWS-907	Westmoreland Rd Verne Ave to Verne Ave	1	61	Westmoreland Rd	Verne Ave	Verne Ave
Water	Procurement	Repair	CS-1909 DWSD	Westwood Elmira to Chicago	7	1,779	Westwood	Elmira	Chicago
Water	Design	Replace	WS-716	Wheeler Rec Center Chrysler to St Antoine	5	720	Wheeler Rec Center	Chrysler	St Antoine
Water	Design	Replace	WS-716	Wheeler Rec Center Chrysler to Beaubien	5	1,172	Wheeler Rec Center	Chrysler	Beaubien
Water	Construction	Repair	WS-707	Whitcomb Pembroke to Vassar	2	1,256	Whitcomb	Pembroke	Vassar
Water	Procurement	Repair	CS-1909 DWSD	Wilkins Beaubien to St. Antoine	6	509	Wilkins	Beaubien	St. Antoine
Water	Procurement	Repair	CS-1909 DWSD	Wilkins St. Antoine to Chrysler Drive	5	757	Wilkins	St. Antoine	Chrysler Drive
Sewer	Procurement	Repair	DWS-916	Wilkins St Antoine to Brush	5	373	Wilkins	Antoine	Brush
Water	Design	Replace	WS-716	Wilkins St Chrysler to Brush	5	1,504	Wilkins St	Chrysler	Brush
Water	Procurement	Repair	CS-1909 DWSD	Winder Beaubien to Chrysler Svc Drive	6	1,180	Winder	Beaubien	Chrysler Svc Drive
Sewer	Procurement	Repair	DWS-916	Winder St Antoine Brush	5	463	Winder	St Antoine	Brush
Water	Design	Replace	WS-716	Winder St Beaubien to St Antoine	5	781	Winder St	Beaubien	St Antoine
Sewer	Construction	Repair	DWS-908	Woodhall Harper to Minvera	4	44	Woodhall	Harper	Minvera
Sewer	Construction	Repair	DWS-908	Woodhall Linville to School Lot	4	311	Woodhall	Linville	School Lot
Sewer	Construction	Repair	DWS-908	Woodhall Munich to Waveney	4	601	Woodhall	Munich	Waveney
Sewer	Construction	Repair	DWS-908	Woodhall Bremen to Mack	4	264	Woodhall	Bremen	Mack
Sewer	Construction	Repair	DWS-908	Woodhall Berden to Linville	4	10	Woodhall	Berden	Linville
Sewer	Construction	Repair	DWS-908	Woodhall Chandler Park to Southampton	4	338	Woodhall	Chandler Park	Southampton
Sewer	Construction	Replace	DWS-908	Woodhall Cornwall to Munich	4	312	Woodhall	Cornwall	Munich
Sewer	Construction	Repair	DWS-908	Woodhall Cornwall to Munich	4	300	Woodhall	Cornwall	Munich
Sewer	Construction	Repair	DWS-908	Woodhall Warren to Cornwall	4	310	Woodhall	Warren	Cornwall
Sewer	Construction	Replace	DWS-908	Woodhall Warren to Cornwall	4	316	Woodhall	Warren	Cornwall
Water	Construction	Replace	WS-712	Woodhall St Chandler Park Dr southeast to Southampton St	4	656	Woodhall St	Chandler Park Dr souther	ast Southampton St
Water	Procurement	Repair	CS-1909 DWSD	Woodmont Fullerton to Schoolcraft	1	2,554	Woodmont	Fullerton	Schoolcraft